



**Texaco Exploration
and Production Inc.**
Denver Region

3300 North Butler
Farmington, NM 87401
505 325-4397

November 4, 1999

Ms. Lisha Cordova
State of Utah Department of Natural Resources
Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P.O. Box 145801
Salt Lake City, Utah 84114-5801

Re: Texaco Year 2000 Drilling Wells
Notice of Staking

Dear Lisha:

Attached for your information please find Texaco Exploration and Production, Inc.'s Notice Of Staking (NOS) forms for each of our thirteen (13) Year 2000 drilling wells. Included with each NOS is a location layout drawing and a project location map showing the referenced well. The original and two copies were submitted to Mr. Eric Jones in the BLM office in Moab, Utah. All of the wells will be on Federal land.

WELL	SECTION	RANGE	TOWNSHIP	FOOTAGE	FOOTAGE	SURF ELEV.	Anticipated Total Depth
22-69	22	18S	7E	870'FNL	562' FEL	6350	3405
22-83	22	18S	7E	480'FSL	1790'FEL	6390	3335
23-84	23	18S	7E	2151'FSL	398'FWL	6200	3140
27-85	27	18S	7E	1690'FNL	2320'FWL	6480	3395
27-86	27	18S	7E	1394'FNL	574'FEL	6390	3230
27-87	27	18S	7E	780'FSL	890'FEL	6740	3560
26-88	26	18S	7E	1816'FNL	897'FWL	6400	3175
35-89	35	18S	7E	1780'FSL	830'FWL	6310	3035
27-90	27	18S	7E	1960'FSL	630'FWL	6550	3500
22-91	22	18S	7E	951'FNL	1973'FWL	6490	3610
3-92	3	18S	7E	605'FSL	1718'FWL	6400	3690
3-93	3	18S	7E	2006'FNL	1233'FWL	6520	3820
21-94	21	18S	7E	512'FNL	547'FEL	6720	3920


Please feel free to contact Richard Carr or myself at the above number if you have any questions.

Sincerely,


Allen R. Davis
Farmington Production Team Leader

cc: Mr. Joe Mc Henry, Texaco
Allen Childs, Talon Resources
Farmington well file

RNC/mc



NOTICE OF STAKING (Not to be used in place of Application for Permit to Drill Form 3160-3)		6. Lease Number UTU-68538
1. Oil Well <input type="checkbox"/> Gas Well <input checked="" type="checkbox"/> Other (Specify)		7. If Indian, Allottee or Tribe Name N/A
2. Name of Operator: Texaco Exploration And Production, Inc.		8. Unit Agreement Name N/A
3. Name of Specific Contact Person: Richard Carr		9. Farm or Lease Name FEDERAL 'T'
4. Address & Phone No. of Operator or Agent 3300 North Butler, Farmington, Nm 87401		10. Well No. 22-83
5. Surface Location of Well Attach: a) Sketch showing road entry onto pad, pad dimensions, and reserve pit. b) Topographical or other acceptable map showing location, access road, and lease boundaries. 480' FSL & 1790' FEL		11. Field or Wildcat Name Undesignated
		12. Sec., T., R., M., or Blk. and Survey or Area 22, T18S, R7E, SLB&M
		13. County, Parish or Borough EMERY
15. Formation Objective Ferron Coals & Sands	16. Estimated Well Depth 3335'	14. State UTAH
17. Additional Information (as appropriate; must include surface owner's name, address, and telephone number) Bureau of Land Management, 125 S. 600 W., Price, UT 84501 (435)636-3640		

18. Signed  Title Production Supervisor


Date October 18, 1999


Note: Upon Receipt of this Notice, the Bureau of Land Management (BLM) will schedule the date of the onsite predrill inspection and notify you accordingly. The location must be staked and access road must be flagged prior to the onsite.

Operators must consider the following prior to the onsite:

- a) H₂S Potential
- b) Cultural Resources (Archaeology)
- c) Federal Right-of-Way or Special Use Permit

(IMPORTANT: SEE REVERSE SIDE FOR INSTRUCTIONS)





Federal 22-83
480' FSL 1790' FEL
SW/4 SE/4
Section 22, T18S, R7E
UTU-68538



Talon Resources, Inc.
 375 South Carbon Avenue, Suite 138
 Price, Utah 84501
 Ph: 435-637-5032 ext. 711
 Fax: 435-748-5085



TEXACO



EXPLORATION & PRODUCTION
LOCATION LAYOUT
Section 22, T18S, R7E, S.L.B.&M.
Federal 22-83

Drawn By
D. Robertson

Checked By
L.W.J.

Drawing No.


Date
10/14/99

P-1

Scale
1" = 50'

Sheet **1** of **1**

Job No.
050



Legend

- ★ 35-6 *Texaco Existing Well Location and Number*
- 27-87 *Proposed Well Location and Number*
- *Main Travel Roads*
Access and/or Upgraded Roads
- - - *Unimproved Road*
- GAC - *Existing Gas and Water*



Talon Resources, Inc.
 375 South Carbon Avenue, Suite 138
 Price, Utah 84501
 Ph: 435-637-5032 ext. 711
 Fax: 435-748-5085

TEXACO
 EXPLORATION & PRODUCTION
 PROJECT LOCATION MAP
 Section 22, T18S, R7E, S.L.B.&M.
Federal 22-83

Drawn by D. Robertson	Checked by L.W.J.
Drawing No. P-1	Date 10/18/99
	Scale 1" = 2000'
Sheet 2 of 2	Job No. 050

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. TYPE OF WORK

DRILL ☒

DEEPEN ☐

b. TYPE OF WELL

OIL WELL ☐

GAS WELL ☒

OTHER

SINGLE ZONE ☒

MULTIPLE ZONE ☐

2. NAME OF OPERATOR

Texaco Exploration and Production, Inc.

3. ADDRESS AND TELEPHONE NO.

3300 North Butler, Farmington, NM 87401;

505-325-4397

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. *)

At surface

539' FSL, 1831' FEL

At proposed prod. zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

3.7 miles northwest of Orangeville, Utah

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drig. unit line, if any)

1831'

16. NO. OF ACRES IN LEASE

2205.82

17. NO. OF ACRES ASSIGNED TO THIS WELL

160 acres

18. DISTANCE FROM PROPOSED LOCATION TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR, ON THIS LEASE, FT. -

2250'

19. PROPOSED DEPTH

3435'

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

6385' GR

22. APPROX. DATE WORK WILL START*

April 2000

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8" K-55 ST&C	24	300'	230 sacks Class G cement + 2% CaCl ₂ + 0.25 pps cellophane flakes
7-7/8"	5-1/2" N-80 LT&C	17	3435'	135 sacks 10:1 RFC Class G cement + 0.25 pps cellophane flakes

RECEIVED

JAN 31 2000

DIVISION OF
OIL, GAS AND MINING

Federal Approval of this
Action is Necessary

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

TITLE FARMINGTON O. U. TEAM LEADER DATE 1/7/2000

(This space for Federal or State office use)

PERMIT NO. 43-015-30452

APPROVAL DATE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY

TITLE

BRADLEY G. HILL
RECLAMATION SPECIALIST III


DATE 2/9/00

*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency or the

Township 18 South

Range 7 East



Legend

- Drill Hole Location
- ⊙ Brass Cap (Found)
- Brass Cap (Searched for, but not found)
- △ Calculated Corner
- () GLO
- GPS Measured

Location:

The Bearings indicated are per the recorded plat obtained from the U.S. Land Office. The well location was determined using a Trimble 4700 GPS survey grade unit.

Basis of Elevation:


Basis of Elevation of 6006.86' being a Utah State Engineer's benchmark located between Section 25 and Section 28, T18S., R9E., Salt Lake Base & Meridian, 350' South of the Northwest Corner of Section 25, Township 18 South, Range 7 East.

Description of Location:

Proposed Drill Hole located in the SW 1/4, SE 1/4 of Section 22; being 539.0' North and 1831.1' West from the Southeast Corner of Section 22, T18S., R7E., Salt Lake Base and Meridian.

Surveyor's Certificate:

I, Albert J. Spensko, a Registered Professional Land Surveyor, holding Certificate 146652 State of Utah, do hereby certify that the information on this drawing is a true and accurate survey based on data of record and was conducted under my personal direction and supervision as shown hereon.



GRAPHIC SCALE



Talon Resources, Inc.
375 South Carbon Avenue, Suite 126
Price, Utah 84501
Ph: 435-837-3032 ext. 711
Fax: 435-748-5085



TEXACO E & P
WELL # 22-83



Section 22, T18S., R7E., S.L.B.&M.
Emery County, Utah

Drawn By: D. Robertson	Checked By: L.W.J.
Drawing No. A-1	Date: 11/19/99
	Scale: 1" = 1000'
Sheet 1 of 4	Job No. 050



Talon Resources, Inc.

Service, Quality and Accuracy

375 South Carbon Avenue A-10
Suite 101
Price, Utah 84501
Phone: 435-637-8781
435-637-5032 Ext 710/711

Cell: 801-650-1401
801-650-1402
Fax: 435-637-7336
Email: talon@castlenet.com

January 26, 2000

Mr. Eric Jones
Petroleum Engineer
82 East Dogwood
Moab, Utah 84532

RECEIVED
JAN 31 2000
DIVISION OF
OIL, GAS AND MINING

RE: Application for Permit to Drill—Federal T 22-83, Emery County, Utah
539' FSL, 1831' FEL, Section 22, T18S, R7E, SLB&M.

Dear Mr. Jones:


On behalf of Texaco Exploration and Production, Inc., Talon Resources, Inc. respectfully submits the enclosed original of the *Application for Permit to Drill (APD)* for the above named well. Included with the APD is the following supplemental information:

- Exhibit "A" - Survey plats and layouts of the proposed well site;
- Exhibit "B" - Proposed location map with pipe, power, and road corridors;
- Exhibit "C" - Drilling site layout;
- Exhibit "D" - Onsite Inspection Checklist;
- Exhibit "E" - Well site layout;
- Exhibit "F" - Typical road cross-section;
- Exhibit "G" - Typical BOP diagram;
- Exhibit "H" - Typical wellhead manifold diagram;
- Exhibit "I" - Right-of-Way plat.

Please accept this letter as Texaco Exploration and Production's written request for confidential treatment of all information contained in and pertaining to this permit application, if said information is eligible for such consideration.

Thank you very much for your timely consideration of this application. Please feel free to contact myself or Mr. Richard Carr at Texaco if you have any questions.

Sincerely,

A handwritten signature in dark ink, appearing to read "Larry W. Johnson", with a long horizontal flourish extending to the right.

Larry W. Johnson
Principal

cc: Mr. Mike Kaminski, BLM, Price, Utah
Mr. John Baza, UDOGM,
Mr. Allen Davis, Texaco
Mr. Richard Carr, Texaco
Texaco Well File



Proposed 2000 wellsite

Federal T 22-83

Texaco Exploration and Production, Inc.

**BUREAU OF LAND MANAGEMENT
MOAB DISTRICT
APPLICATION FOR PERMIT TO DRILL
ON-SITE INSPECTION CHECKLIST**

Operator: Texaco Exploration and Production, Inc
Lease and Well Name: Federal T 22-83
Location: SW/4 SE/4, Section 22, T18S, R7E, SLB&M
Onsite Inspection Date: None

All operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, the approved plan of operations and the conditions of approval. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

1. **Surface Formation and Estimated Formation Tops:**

<u>Formation</u>	<u>Depth</u>
Bluegate Shale	100'
Top of "A" Coal	3005'
Total Depth	3435'

2. **Estimated Depths at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered:**

Expected Oil Zones:	None
Expected Gas Zones:	Ferron coals at 3005'to 3135'
Expected Water Zones:	Ferron coals at 3005'to 3135'
Expected Mineral Zones:	None

All Fresh water and prospectively valuable minerals encountered during drilling will be recorded by depth and will be cased and cemented. When possible, water flow rates will be measured and samples will be taken and analyzed with the results being submitted to the BLM. All oil and gas shows will be tested to determine commercial potential.

3. **Pressure Control Equipment:**

The proposed pressure control equipment consists of the following:

- a. Rotating head
 - b. 3000 psi WP hydraulic-operated double ram
- (See attached schematic drawings of the BOP and choke manifold)

BOP systems shall be consistent with API RP53 and Onshore Oil and Gas Order No. 2. Pressure tests for the surface casing and all BOP equipment potentially subject to pressure will be conducted before drilling the surface casing shoe. Blowout preventer controls will be installed prior to drilling the surface casing shoe and will remain in use until the well is completed or abandoned. BOP equipment will be inspected and operated daily to ensure good mechanical working order. The ram preventers shall be inspected and operated each trip (no more than once a day is require).

Pressure tests will be performed on all related well control equipment. Ram type preventers and associated equipment shall be tested using a test plug to full working pressure. The test pressure shall be maintained for at least 10 minutes with no bleed off. The valve on the casing head below the test plug shall be open during the BOP test.

As a minimum, the above pressure test shall be performed when:

- a. The stack is initially installed (prior to drilling out of the surface casing),
- b. Any seal subject to pressure is broken,
- c. Following repairs to any part of the BOP system, and
- d. At 30 day intervals.

All valves shall be tested from the working pressure side with all downstream valves open.

A BOP pit level drill shall be conducted weekly for each drilling crew.

All of the above described tests and drills shall be recorded in the drilling log. Test charts, with individual test results identified, shall be maintained on location while drilling and shall be available upon request.

Drill string safety valves to fit all tools in the drill string shall be maintained on the rig floor while drilling operations are in progress.

4. **Casing Program and Auxiliary Equipment:**

- a. The following surface casing will be set at 300' in a 12-1/4" hole:
8-5/8" 24 lbs/ft K-55 ST&C (new ERW pipe)
- b. The following production casing will be set at 3435' (TD) through the Ferron coal section in a 7-7/8" hole:
5-1/2" 17 lbs/ft N-80 LT&C (new ERW pipe)

5. **Cement Program:**

<u>Surface:</u>	<u>Type and Amount</u>
0' to 300' (TOC at surface)	230 sacks Class G cement + 2% CaCl ₂ + 0.25 pps cellophane flakes Yield: 1.16 cf/sack Weight: 15.8 ppg (The above volume assumes 100% excess over gauge hole)

<u>Production:</u>	<u>Type and Amount</u>
2535' to 3435' (TOC at 2535')	135 sacks 10:1 RFC Class G cement + 0.25 pps cellophane flakes Yield: 1.62 cf/sack Weight: 14.2 ppg (The above volume assumes 50% excess over gauge hole)

6. **Mud Program:**

<u>Interval</u>	<u>Mud Type</u>	<u>Mud Weight</u>	<u>Viscosity</u>
0' - 300'	Air	N/A	N/A
300' - TD	Air	N/A	N/A

The Blooie line will be approximately 100' in length and will extend in a straight line from below the rotating head as shown in the attached Rig Layout schematic. An automatic spark-type igniter will be affixed to the end of the blooie line and set to provide a continuous spark to ignite and burn any produced hydrocarbon gas. Dedusting will be accomplished with a small pump, water line and spray nipple affixed near the end of the blooie line to provide a continuous spray of water. It is not planned to have any standby fluid on location, however if it is necessary to fill the hole with fluid, produced Ferron coal water will be trucked in as necessary from a nearby evaporation pit.

In the event the hole gets wet, either mist or produced Ferron coal water treated with bactericide will be used as a circulating medium. Due to the potential for contamination of usable quality water aquifers, material containing chromates will not be used in the circulating medium.

7. **Coring Logging and Testing Program:**

- a. No drill stem test is planned.
- b. No coring is planned
- c. The logging program will consist of a GR-CNL-LDT log from 2000' to TD, an AITH (array induction) log from base of the surface casing to TD, and an HRCL (high-resolution coal log) from 3000' to TD.

8. **Abnormal Conditions, Bottom Hole Pressures and Potential Hazards:**

- a. The maximum anticipated bottom hole pressure gradient in any of the zones to be penetrated is 8.33 ppg (fresh water gradient).
- b. Lost circulation is a potential hazard in the Ferron coal section in the event the hole gets wet and water must be used as the circulating medium.
- c. No abnormal temperatures are anticipated.
- d. No H₂S gas is anticipated.

9. **Lessee's Operator's Representatives:**

Permit Matters

Texaco Exploration and Production, Inc.
Ron Wirth
Production Supervisor
P.O. Box 618
Orangeville, Utah 84537

Drilling and Completion Matters

Texaco Exploration and Production, Inc.
David Wojahn
Drilling Engineer
4601 DTC Boulevard
Denver, Colorado 80237
(303) 793-4918
(303) 793-4000 (switchboard)
(303) 771-0866 (home)

Bureau of Land Management
Moab District
Application for Permit to Drill
On-Site Inspection Checklist

Company: Texaco Exploration & Production, Inc. Well No.: Federal 22-83

Location: Section 22, T18S R7E SLB & M

Lease No.: Federal UTU-68538

On-Site Inspection Date: January 20, 2000

B. THIRTEEN POINT SURFACE USE PLAN

The dirt contractor will be provided with an approved copy of the surface use plan of operations before initiating construction.

1. Existing Roads:

- a. Proposed route to location: *See Exhibit "B".*
- b. Location of proposed well in relation to town or other reference point: *Approximately 3.7 miles northwest of Orangeville, UT.*
- c. Contact the County Road Department for use of county roads. The use of Emery County roads will require an encroachment permit from the Emery County Road Department.:
N/A
- d. Plans for improvement and/or maintenance of existing roads: *N/A*
- e. Other:

2. Planned Access Roads:

- a. Location (centerline): *From the proposed Federal 23-84 access road, approximately 2200' FSL, 300' FEL, Section 23, T18S, R7E*
- b. Length of new access to be constructed: *Approximately 100'*
- c. Length of existing roads to be upgraded: *Approximately 2500'*
- d. Maximum total disturbed width: *60'*
- e. Maximum travel surface width: *25'*
- f. Maximum grades: *10%*
- g. Turnouts: *None*
- h. Surface materials: *Native*
- i. Drainage (crowning, ditching, culverts, etc): *Roads will be crowned with bar ditches on both sides with approximately 12 culverts placed along new road.*

- j. Cattleguards: *No cattleguards will be needed, Gates will be installed if required.*
- k. Length of new and/or existing roads which lie outside the lease boundary for which a BLM right-of-way is required: *Approximately 400', see Exhibit "I".*
- l. Other:

Surface disturbance and vehicular travel will be limited to the approved location access road. Any additional area needed must be approved by the Area Manager in advance.

If a right-a-way is necessary, no surface disturbing activities shall take place on the subject right-of-way until the associated APD is approved. The holder will adhere to conditions of approval in the Surface Use Program of the approved APD, relevant to any right-of-way facilities.

If a right-of-way is secured, boundary adjustments in the lease or unit shall automatically amend this right-of-way to include that portion of the facility no longer contained within the lease or unit. In the event of an automatic amendment to this right-of way grant, the prior onlease/unit conditions of approval of this facility will not be affected even though they would now apply to facilities outside of the lease/unit as a result of a boundary adjustment. Rental fees, if appropriate shall be recalculated based on the conditions of this grant and the regulations in effect at the time of an automatic amendment.

If the well is productive, the access road will be rehabilitated or brought to Resource (Class III) Road standards within 60 days of dismantling the rig. If upgraded, the access road must be maintained at these standards until the well is properly abandoned. If this time frame cannot be met, the Area Manager will be notified so that temporary drainage control can be installed along the access road.

- 3. Location of Existing Wells - on a map, show the location of all water, injection, disposal, producing and drilling wells within a one mile radius of the proposed well, and describe the status of each: *See Exhibit "B"*
- 4. Location of Production Facilities:
 - a. On-site facilities: *See Exhibit "E"*
 - b. Off-site facilities: *None*
 - c. Pipelines: *N/A*

All permanent (in place for six months or longer) structures constructed or installed (including oil well pump jacks) will be painted a flat, nonreflective color to match the standard environmental colors, as determined by the Rocky Mountain Five-State Interagency Committee. All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) may be excluded. Colors will be as follows: olive black

All site security guidelines identified in 43 CFR 3163.7-5 and Onshore Oil and Gas Order No. 3 Colors will be as follows: olive black

If a gas meter run is constructed, it will be located on lease within 500 feet of the wellhead. The gas flowline will be buried from the wellhead to the meter and will be buried downstream of the meter until it leaves the pad. Meter runs will be housed and/or fenced. The gas meter shall be calibrated prior to first sales and shall be calibrated quarterly thereafter. All gas production and measurement shall comply with the provisions of 43 CFR 3162. 7-3, Onshore Oil and Gas Order No. 5, and American Gas Association (AGA) Report No. 3.

If a tank battery is constructed on this lease, it will be surrounded by a dike of sufficient capacity to contain 1 ½ times the storage capacity of the largest tank. All loading lines and valves will be placed inside the berm surrounding the tank battery. All oil production and measurement shall conform to the provisions of 43 CFR 3162.7-3 and Onshore Oil and Gas Order No. 4.

Production facilities on location may include a lined or unlined produced water pit. If water is produced from the well, an application must be submitted.

5. Location and Type of Water Supply:

All water needed for drilling purposes will be obtained from (describe location and/or show on A map): *All water needed for drilling will be obtained from a local municipal water source. Since this well will be primarily drilled with air, minimal water will be needed.*

6. Source of Construction Material:

Pad construction material will be obtained from (if the source is Federally owned, show location on a map): *Private Owner*

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

Any gravel used will be obtained from a state approved gravel pit.

7. Methods of Handling Waste Disposal:

Describe the methods and locations proposed for safe containment and disposal of waste material, e.g. cuttings, produced water, garbage, sewage, chemicals, etc.

The reserve pit will be located: *Inbound and along the south side of the pad.*

The reserve pit will be constructed so as not to leak, break, or allow discharge

The reserve pit will be lined with native material unless designated otherwise by BLM officers prior to construction. Pit walls will be sloped no greater than 2 to 1.

The reserve pit shall be located in cut material, with at least 50% of the pit volume being below original ground level. Three sides of the reserve pit will be fenced before drilling starts. The fourth side will be fenced as soon as drilling is completed, and shall remain until the pit is dry. As soon as the reserve pit has dried, all areas not needed for production will be rehabilitated.

Trash must be contained in a trash cage and hauled away to an approved disposal site as necessary but no later than at the completion of drilling operations.

8. Ancillary Facilities: Garbage Containers and Portable Toilets

9. Well Site Layout - depict the pit, rig, cut and fill, topsoil, etc. on a plat with a scale of at least 1" = 50'.

All well, whether drilling, producing, suspended, or abandoned, will be identified in accordance with 43 CFR 3162.6.

Access to the well pad will be from: *East*

The blooie line will be located: *At least 100 feet from the well head.*

To minimize the amount of fugitive dust and spray escaping from the blooie pit, the following blooie line deflection method will be employed: *Water Injection*.

10. Plans for Restoration of the Surface:

The top 6 inches of topsoil material will be removed from the location and stockpiled separately on: *Adjacent land*.

Topsoil along the access road will be reserved in place adjacent to the road.

Immediately upon completion of drilling, all equipment that is not necessary for production shall be removed.

The reserve pit and that portion of the location not needed for production will be reclaimed.

Before any dirt work to restore the location takes place, the reserve pit must be completely dry.

Reclaimed roads will have the berms and cuts reduced and will be closed to vehicle use.

All disturbed areas will be recontoured to replicate the natural slope.

The stockpiled topsoil will be evenly distributed over the disturbed area.

Prior to reseeding, all disturbed areas, including the access roads, will be scarified and left with a rough surface.

Seed will be broadcast or drilled between Sept. and Nov., or at a time specified by the BLM. If broadcast, a harrow or some other implement will be dragged over the seeded area to assure seed coverage.

The following seed mixture will be used: *BLM-recommended mixture*.

The abandonment marker will be one of the following, as specified by BLM:

- 1) at least four feet above ground level,
- 2) at restored ground level, or
- 3) below ground level.

In any case the marker shall be inscribed with the following: operator name, lease number, Well name and surveyed description (township, range, section and either quarter-quarter or footage.).

Additional requirements:

11. Surface and Mineral Ownership: *Federal; Bureau of Land Management*

12. Other Information:

- a. Archeological Concerns: *None that the operator is aware of.*

The operator is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing

historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator is to immediately stop work That might further disturb such materials, and contact the authorized officer (AO). Within five (5) working days, the AO will inform the operator as to:

1. whether the materials appear eligible for the National Register of Historic Places;
2. the mitigation measures the operator will likely have to undertake before the site can be used (assuming in situ preservation is not necessary); and
3. a time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

If the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible for mitigation costs. The AO will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the AO that the required mitigation has been completed, the operator will then be allowed to resume construction.

- b. Threatened and Endangered Species Concerns: *None that the operator is aware of.*
- c. Wildlife Seasonal Restrictions (yes/no): *See Environmental Impact Statement (EIS)*
- d. Off Location Geophysical Testing: *N/A*
- e. Drainage crossings that require additional State or Federal approval: *None*
- f. Other:

13. Lessee's or Operator's Representative and Certification

Representative: Texaco Exploration & Production, Inc.

Name: Allen R. Davis

Title: Team Leader / Farmington Operating Unit


Address: 3300 No. Butler Suite 100
Farmington, New Mexico 87401

Phone No: 505-325-4397

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exists; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Texaco and its contractors and subcontractors in conformity with this APD package and the terms and conditions under which it is approved. I also certify responsibility for the operations conducted on that portion of the leased lands associated with this application, with bond coverage being provided under Texaco's BLM bond. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Signature: _____



Date: _____

1/7/2000

Title: Team Leader

C. REQUIRED APPROVALS, REPORTS AND NOTIFICATIONS

Required verbal notifications are summarized in Table 1, attached.

Building Location - Contact the Resource Area, Natural Resource Protection Specialist at least 24 hours prior to commencing construction of location.

Spud - The spud date will be reported to the Resource Area Office 24 hours prior to spudding. Written notification in the form of a Sundry Notice (Form 3160-5) will be submitted the District Office within 24 hours after spudding, regardless of whether spud was made with a dry hold digger or big rig.

Daily Drilling Reports - Daily drilling reports shall detail the progress and status of the well and shall be submitted to the District Office on a weekly basis.

Monthly Reports of Operations - In accordance with Onshore Oil and Gas Order No. 1, this well shall be reported on Minerals Management Service (MMS) Form 3160, "Monthly Report of Operations," starting the month in which operations commence and continuing each month until the well is physically plugged and abandoned. This report will be filed directly with MMS.

Sundry Notices - There will be no deviation from the proposed drilling and/or workover program without prior approval from the Assistant District Manager. "Sundry Notices and Reports on Wells: (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2. Safe drilling and operating practices must be observed.

Drilling suspensions - Operations authorized by this permit shall not be suspended for more than 30 days without prior approval of the Authorized Officer. All conditions of this approval shall be applicable during any operations conducted with a replacement rig.

Undesirable Events - Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be immediately reported to the Resource Area in accordance with requirements of NTLA.

Cultural Resources - If cultural resources are discovered during construction, work that might disturb the resources is to stop, and the Area Manager is to be notified.

First production - Should the well be successfully completed for production, the Assistant District Manager, Minerals Division will be notified when the well is placed in producing status. Such notification may be made by phone, but must be followed by a sundry notice or letter not later than five (5) business days following the date on which the well is placed into production.

A first production conference will be scheduled as soon as the productivity of the well is apparent. This conference should be coordinated through the Resource Area Office. The Resource Area Office shall be notified prior to the first sale.

Well Completion Report - Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted to the District Office not later than thirty (30) days after completion of the well or after completion operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs, core descriptions, core analysis, well test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings and/or samples) will be submitted when requested by the Assistant District Manager.

Venting/Flaring of Gas - NTL-4A allows venting/flaring of gas during the initial well evaluation period not to exceed 30 days or 50 Mmcf. Venting/flaring beyond the initial test period threshold must be approved by the District Office.

Produced Water - Produced waste water may be confined to an unlined pit for a period not to exceed 90 days after initial production. During the 90 day period, an application for approval of a permanent disposal method and location, along with the required water analysis, will be submitted to the Assistant District Manager for approval.

Off-Lease Measurement, Storage, Commingling - Prior approval must be obtained from the Assistant District Manager for off-lease measurement, off-lease storage and/or commingling (either down-hole or at the surface).

Plugging and Abandonment - If the well is completed as a dry hole, plugging instructions must be obtained from the BLM, Moab District Office prior to initiating plugging operations. Table 1 of this document provides the after-hours phone numbers of personnel who are authorized to give plugging instructions.

A "Subsequent Report of Abandonment" (Form 3160-5) will be filed with the Assistant District Manager, Minerals Divisions within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Upon completion of approved plugging, a regulation marker will be erected in accordance with 43 CFR 3162.6. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the Area Manager or his representative, or the appropriate surface managing agency.

TABLE 1
NOTIFICATIONS

Notify Michael Kaminski of the Price Resource Area, at (435) 636-3646 for the following:

2 days prior to commencement of dirt work construction or reclamation;

1 day prior to spudding

50 feet prior to reaching surface and intermediate casing depths;

3 hours prior to testing BOPE;

12 hours prior to reaching kickoff point depth (if applicable).


If the person at the above number cannot be reached, notify the Moab District Office at (435) 259-6111. If unsuccessful, notify one of the people listed below.

Well abandonment operations require 24 hour advance notice and prior approval. In the case of newly drilled dry holes, verbal approval can be obtained by calling the Moab District Office, Branch of Fluid Minerals at (435) 259-6111. If approval is needed after work hours, you may contact the following:

Eric Jones, Petroleum Engineer

Office: (435) 259-6111

Home: (435) 259-2214




Talon Resources, Inc.
 375 South Carbon Avenue, Suite 138
 Price, Utah 84501
 Ph: 435-637-5032 ext. 711
 Fax: 435-748-5085

TEXACO E & P
LOCATION LAYOUT
 Section 22, T18S., R7E., S.L.B. & M.
WELL # 22-83


Drawn By: D. Robertson	Checked By: L.W.J.
Drawing No. A-2	Date: 11/22/99
	Scale: 1" = 60'
Sheet 2 of 4	Job No. 050

Elevation Ungraded Ground at Location Stake = 6384.9'
Elevation Graded Ground At Location Stake = 6382.4'


Slope - 1 1/2:1
(Except Pit)
Pit Slope = 1:1




View C-C



View B-B



View A-A



Approximate Yardages


Cut
(6") Topsoil Stripping = 750.00 Cu. Yds.
Remaining Location = 2331.10 Cu. Yds.
TOTAL CUT = 3081.00 Cu. Yds.
TOTAL FILL = 1946.60 Cu. Yds.



Talon Resources, Inc.
375 South Carbon Avenue, Suite 128
Price, Utah 84501
Ph: 435-637-5032 ext. 711
Fax: 435-748-5085

★ **TEXACO E & P** ★
TYPICAL CROSS SECTIONS
Section 22, T18S., R7E., S.L.B.&M.
WELL # 22-83

Drawn By: D. Robertson	Checked By: L.W.J.
Drawing No. C-1	Date: 11/18/99
	Scale: As Shown
Sheet 3 of 4	Job No. 050



Legend

- ★ 35-6 Tezaco Existing Well Location & Number
- 27-87 Proposed 2000 Well Location & Number
- 11-70 Proposed 1999 Well Location & Number
- Main Travel Roads
- Access and/or Upgraded Roads
- Existing Power
- Existing Gas and Water
- Unimproved Road
- Proposed Road, Gas, Water, & Power
- Proposed Road
- Proposed Gas, Water & Power
- Proposed Power



Talon Resources, Inc.
 375 South Carbon Avenue, Suite 138
 Price, Utah 84501
 Ph: 435-637-5032 ext. 711
 Fax: 435-748-5085





TEXACO



EXPLORATION & PRODUCTION
LOCATION MAP
 Section 22, T18S, R7E, S.L.B.&M.
Well # 22-83

Drawn By D. Robertson	Checked By L.W.J.
Drawing No. L-1	Date 12/13/99
	Scale 1" = 2000'
Sheet 4 of 4	Job No. 050







DIESEL FUEL 26' PROPA



4'



LIGHT PLANT



APPROXIMATE LAYOUT OF UNIT & EQUIPMENT
(Not to Scale)

EXHIBIT "C"



ANCHOR (Typ. 4 Pl)

74'
140' 120'
70'

ROAD

WATER PIPELINE
GAS PIPELINE

3-PHASE
ELECTRIC

WELL
HEAD

GAS/WATER

PUMPING
UNIT

MOTOR

RTU
STARTER

TRANSFORMER


SEPARATOR

TEXACO EXPLORATION & PRODUCTION
WELL SITE LAYOUT
260' X 144'



EXHIBIT "E"

TEXACO INC.



TYPICAL ROAD CROSS-SECTION
NOT TO SCALE

EXHIBIT "F"



BOP Equipment

3000psi WP (except rotating head at 1000psi)




EXHIBIT "G"



CHOKE MANIFOLD




EXHIBIT "H"



WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 01/31/2000

API NO. ASSIGNED: 43-015-30452

WELL NAME: FEDERAL T 22-83

OPERATOR: TEXACO E & P INC (N5700)

CONTACT: ALLEN DAVIS

PHONE NUMBER: 505-325-4397

PROPOSED LOCATION:

SWSE 22 180S 070E

SURFACE: 0539 FSL 1831 FEL

BOTTOM: 0539 FSL 1831 FEL

EMERY

UNDESIGNATED (2)

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-68538

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: FRSD

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering		
Geology		
Surface		

RECEIVED AND/OR REVIEWED:

☒ Plat

☒ Bond: Fed ☒ Ind ☐ Sta ☐ Fee
(No. CO 0058) XBLM 2/9/00

☐ Potash (Y/N)

☐ Oil Shale (Y/N) *190 - 5 (B)

☒ Water Permit

(No. MUNICIPAL)

☐ RDCC Review (Y/N)

(Date: _____)

N/A Fee Surf Agreement (Y/N)

LOCATION AND SITING:

☐ R649-2-3. Unit _____

☐ R649-3-2. General

Siting: _____

☐ R649-3-3. Exception

☒ Drilling Unit

Board Cause No: 245-1 (160')


Eff Date: 7-7-99

Siting: 460' fr. Dr. Unit Boundary & 920' between wells

☐ R649-3-11. Directional Drill

COMMENTS:

STIPULATIONS: (1) FEDERAL APPROVAL



Utah Oil Gas and Mining


Serving the Industry, Protecting the Environment

OPERATOR: TEXACO E&P INC.. (N5700)

FIELD: UNDESIGNATED (002) BUZZARD BENCH (132)

S EC. 21, 22, 23, 26, 27, 35, T18S, R7 E,

COUNTY: EMERY CAUSE: 245-1 160 ACRES



PREPARED
DATE: 7-Feb-2000



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Kathleen Clarke
Executive Director

Lowell P. Braxton
Division Director

1594 West North Temple, Suite 1210

PO Box 145801

Salt Lake City, Utah 84114-5801

801-538-5340

801-359-3940 (Fax)

801-538-7223 (TDD)

February 9, 2000

Texaco Exploration & Production, Inc.
3300 North Butler
Farmington, New Mexico 87401

Re: Federal T 22-83 Well, 539' FSL, 1831' FEL, SW SE, Sec. 22, T. 18 S, R. 7 E,
Emery County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-015-30452.

Sincerely,

John R. Baza
Associate Director

jb

Enclosures

cc: Emery County Assessor
Bureau of Land Management, Moab District Office

Operator: Texaco E&P Inc.

Well Name & Number: Federal T 22-83

API Number: 43-015-30452

Lease: UTU-68538

Location: SW SE **Sec.** 22 **T.** 18 S. **R.** 7 E.

Conditions of Approval

1. **General**

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. **Notification Requirements**

Notify the Division within 24 hours following spudding the well or commencing drilling operations. Contact Jim Thompson at (801)538-5336.
Notify the Division prior to commencing operations to plug and abandon the well.
Contact John R. Baza at (801)538-5334.

3. **Reporting Requirements**

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. **State approval of this well does not supersede the required Federal Approval which must be obtained prior to drilling.**



Texaco Exploration
and Production Inc.
Denver Region

3300 North Butler
Farmington, NM 87401
505 325-4397

February 9, 2000

State of Utah
Department of Natural Resources
Division of Oil, Gas and Mining
Ms. Lisha Cordova
1594 West North Temple, Suite 1210
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RECEIVED

FEB 14 2000

DIVISION OF
OIL, GAS AND MINING

Re: **Bond Coverage**
Application for Permit to Drill

WELL	SECTION	RANGE	TOWNSHIP	COUNTY	STATE
Utah Fed "T" 22-69	22	18S	7E	Emery	Utah
Utah Fed "T" 22-83	22	18S	7E	Emery	Utah
Utah Fed "C" 23-84	23	18S	7E	Emery	Utah
Utah Fed "T" 27-85	27	18S	7E	Emery	Utah
Utah Fed "T" 27-86	27	18S	7E	Emery	Utah
Utah Fed "T" 27-87	27	18S	7E	Emery	Utah
Utah Fed "A" 26-88	26	18S	7E	Emery	Utah
Utah Fed "A" 35-89	35	18S	7E	Emery	Utah
Utah Fed "T" 27-90	27	18S	7E	Emery	Utah
Utah Fed "T" 22-91	22	18S	7E	Emery	Utah
Utah Fed "P" 3-92	3	18S	7E	Emery	Utah
Utah Fed "P" 3-93	3	18S	7E	Emery	Utah
Utah Fed "T" 21-94	21	18S	7E	Emery	Utah

Dear Lisha:

The Bond Coverage for the above referenced wells is provided by U.S. Dept. of Interior Federal Oil & Gas Lease Bond No. 5858552 and State of Utah Bond No.s 5858501 & 5858502 issued by General Insurance Company of America.

Please accept this letter as Texaco Exploration and Production Incorporated's written request for confidential treatment of all information contained in and pertaining to these permit applications, if said information is eligible for such consideration.

Thank you very much for your timely consideration of these applications. Please feel free to contact me at the above number (ext. 12) if you have any questions.

Sincerely,

Richard Carr
Texaco E. & P. Inc.
Farmington Operating Unit

RNC/rnc



Talon Resources, Inc.

Service, Quality and Accuracy

375 South Carbon Avenue A-10
Suite 101
Price, Utah 84501
Phone: 435-637-5032 Ext 710
435-637-8781

Cell: 435-650-1401
435-650-1402
Fax: 435-637-7336
Email: talon@castlenet.com

February 15, 2000

RECEIVED
FEB 17 2000
DIVISION OF
OIL, GAS AND MINING

Mr. Eric Jones—Petroleum Engineer
Bureau of Land Management—Moab Office
82 East Dogwood
Moab, Utah 84532

RE: Additional information to be included in the previously submitted Texaco Exploration and Production *Applications for Permit to Drill*.

Dear Mr. Jones:


Following are numerous sundry notices (Form 5) to supplement the previously submitted Texaco Exploration and Production, Inc. *Applications for Permit to Drill*. Sundry Notices have been included for all submitted well sites for proposed utility dimensions needed to supplement the previously submitted APD's. Numerous sundry notices are also included for hydrologic evaluations performed on drainages requiring evaluation per the Federal EIS. A sundry notice is also included for a Right-of-Way plat that was previously missing in the Federal T 22-83 application. This concludes all of the supplemental information that should be required for the 13 previously submitted applications.

A copy of this information has been sent to Mr. Mike Kaminski of the BLM Price, Utah office.

Please review the enclosed submissions and contact us if there are any changes to be made.

Please feel free to contact me if you should have any questions or require additional information.

Sincerely,


Larry W. Johnson
Principal

Enclosures

CC: Mr. Mike Kaminski, BLM, Price, Utah
Mr. John Baza, UDOGM
Mr. Allen Davis, Texaco
Mr. Richard Carr, Texaco
Texaco well file

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil ☒ Gas ☐

2. Name of Operator

Texaco Exploration & Production

3. Address and Telephone No.

3300 N. Butler, Suite 100, Farmington, New Mexico 87401

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

539' FSL, 1831' FEL
SW/4 SE/4, Section 22, T18S, R7E, SLB&M

5. Lease Designation and Serial No.

UTU-68538

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

N/A

8. Well Name and No.

Federal T 22-83

9. API Well No.

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Emery County, Utah

12. CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent
☒ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION

- ☐ Change of Name
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ ROW Plat

- Pipeline, Powerline, Maintenance Corridor Construction
☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

The following Right-of-Way Plat was inadvertently left out of the previously submitted Application for Permit to Drill for the Federal T 22-83. Please include the following plat as Exhibit "I" within the Federal T 22-83 application.

RECEIVED
FEB 17 2000
DIVISION OF
OIL, GAS AND MINING

14. I hereby certify that the foregoing is true and correct

Signed

Ron With

Title

PRODUCTION SUPERVISOR

Date

2/15/00

(This space for Federal or State office use)

Approved by

Title

Date



Conditions of approval, if any:

CLASS III ROAD, 6" to 12" GAS PIPELINE
8" TO 16" WATER PIPELINE, 3-PHASE OVERHEAD POWER
United States of America

BEGINNING AT A POINT 569.9' SOUTH, AND 3.7" WEST OF THE WEST QUARTER SECTION CORNER OF SECTION 23, T18S, R7E, S.L.B.&M. THENCE S70°04'51"E, 32.02'; THENCE N85°39'24"E, 137.56' THENCE N74°24'47"W, 83.35'; TO A POINT ON THE FEDERAL C 23-84 WELLSITE, LOCATED WITHIN THE NW/4 OF THE SW/4 OF SAID SECTION 23.

I, Albert J. Spensko, a Registered Professional Land Surveyor, holding Certificate 146652 State of Utah, do hereby certify that the information on this drawing is a true and accurate survey based on data of record and was conducted under my personal direction and supervision as shown hereon.


DATE: BY:



RECEIVED

FEB 17 2000

DIVISION OF OIL, GAS AND MINING



DESTINATION OF DOCUMENT		
Company / Agency	Office Location	Submission Date
* BUREAU OF LAND MANAGEMENT	Price and Moab Field Offices	
TEXACO E & P	Farmington and Oranville Offices	

Technical Group

375 South Carbon Ave.
Price, Utah 84501
Phone (435)637-5032 ex71
FAX (435)637-7336

TEXACO
E&P
Federal T 22-83 Right-of-Way
CORRIDOR RIGHT-OF-WAY DESCRIPTION

DRAWN BY:
JT, DH
CHECKED BY:
LWJ
DATE:
01/27/00
SCALE:
1" = 400'
JOB NO.
070
DRAWING NO.

A-1

SHEET 1 OF 1

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil ☒ Gas ☐

2. Name of Operator

Texaco Exploration & Production, Inc.

3. Address and Telephone No.

3300 N. Butler, Suite 100, Farmington, New Mexico 87401

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

539' FSL, 1831' FEL
SW/4 SE/4, Section 22, T18S, R7E, SLB&M

5. Lease Designation and Serial No.

UTU-68538

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

N/A

8. Well Name and No.

Federal T 22-83

9. API Well No.

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Emery County, Utah

12. CHECK APPROPRIATE BOX (s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

- ☐
- Notice of Intent
-
- ☒
- Subsequent Report
-
- ☐
- Final Abandonment Notice

- ☐
- Change of Name
-
- ☐
- Recompletion
-
- ☐
- Plugging Back
-
- ☐
- Casing Repair
-
- ☐
- Altering Casing
-
- ☒
- Hydrologic Evaluation

- ☐
- Change of Plans
-
- ☐
- New Construction
-
- ☐
- Non-Routine Fracturing
-
- ☐
- Water Shut-Off
-
- ☐
- Conversion to Injection
-
- ☐
- Dispose Water

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Following is the Hydrologic Evaluation for the Federal T 22-83 for drainages requiring design per the Federal Environmental Impact Statement. Please include the following with the previously submitted Application for Permit to Drill.

RECEIVED
FEB 17 2000
DIVISION OF
OIL, GAS AND MINING

14. I hereby certify that the foregoing is true and correct

Signed Ron With Title PRODUCTION SUPERVISOR Date 2/14/00

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____

Conditions of approval, if any:

Crossing #4

Figure 4 shows the very small watershed above crossing #4 with a drainage area of only 0.05 sq. mi. (30 acres). The figure was derived from the DEMs of the quads.

Table 7 gives the flood flows for different return periods from this area as determined from the NFF analysis. The 10-yr. flood is 7 cfs and the 50-yr. flood is 32 cfs. However, the NFF method tends to underestimate the flows at low return periods for very small areas.

Therefore, the Rational method ($Q = CIA$) was applied to this area A of 30 ac. using a runoff coefficient C of 0.25 and a precipitation intensity I of 2 in./hr. The flow Q from this calculation of 15 cfs was used as the 10-yr. flood (see insert in Table 7).

Table 8 shows the results of using a 2.5 ft. diameter culvert 25 ft. long through a 5 ft. high road embankment. The channel at crossing #4 is deep enough for a higher road, but the small flows and small culvert do not require a higher embankment. The road can be sloped down to the 5 ft. height and back up on the other side unless this makes the road too steep.

The 10-yr. 15 cfs flow will pass through the 2.5 ft. culvert with no head (at a depth of 2.04 ft.). The 50-yr. 32 cfs will easily pass through the culvert with no overtopping of the 5 ft. high road.

We also tried a 2.25 ft. (27 in.) culvert if this size is available. Table 9 shows the results of using this 25 ft. long culvert through the 5 ft. high road embankment. The 15 cfs flow will pass through this culvert with no head (at a depth of 2.21 ft.). The 32 cfs will just barely pass through this culvert with no overtopping of the road.




Figure 4. Map of Culvert Crossing #4

Table 7. 10 & 50 Year Flows at Crossing #4

Flow data computed with the National Flood Frequency Program in WMS.
Utah, Basin: 1B, Total Area (sq mi): 0.05

High Plateaus

Mean Basin Elevation (ft) E*: 6490.00 7470.00 10500.00

MAXIMUM FLOOD ENVELOPE: 295 (cfs)

Recurrence Interval	Peak (cfs)	Std Error	Equiv. Years
Rural Peak Q2	1	66.0	N/A
Rural Peak Q5	3	53.0	N/A
Rural Peak <u>Q10</u>	<u>7 (15)</u>	53.0	N/A
Rural Peak Q25	18	57.0	N/A
Rural Peak <u>Q50</u>	<u>32</u>	62.0	N/A
Rural Peak Q100	54	68.0	N/A
Rural Peak Q500	91	N/A	N/A

Table 8. Culvert Size, Head, & Flows at Crossing #4

FHWA CULVERT ANALYSIS
HY-8, VERSION 6.0

C	SITE DATA			CULVERT SHAPE, MATERIAL, INLET				
U	INLET	OUTLET	CULVERT	BARRELS	SPAN	RISE	MANNING	INLET
L	ELEV.	ELEV.	LENGTH	SHAPE	(ft)	(ft)	n	TYPE
V	(ft)	(ft)	(ft)	MATERIAL				
NO.								
1	100.00	99.50	<u>25.00</u>	1 CSP	<u>2.50</u>	<u>2.50</u>	.024	CONVENTIONAL

SUMMARY OF CULVERT FLOWS (cfs)

FILE: BUZFOUR

DATE: 01-29-2000


ELEV (ft)	TOTAL	1	2	3	4	5	6	ROADWAY	ITR
100.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.00	1
101.16	5.0	5.0	0.0	0.0	0.0	0.0	0.0	0.00	1
101.59	10.0	10.0	0.0	0.0	0.0	0.0	0.0	0.00	1
<u>102.04</u>	<u>15.0</u>	15.0	0.0	0.0	0.0	0.0	0.0	0.00	1
102.50	20.0	20.0	0.0	0.0	0.0	0.0	0.0	0.00	1
103.01	25.0	25.0	0.0	0.0	0.0	0.0	0.0	0.00	1
103.60	30.0	30.0	0.0	0.0	0.0	0.0	0.0	0.00	1
104.30	35.0	35.0	0.0	0.0	0.0	0.0	0.0	0.00	1
104.99	40.0	39.2	0.0	0.0	0.0	0.0	0.0	0.00	30
105.07	45.0	39.7	0.0	0.0	0.0	0.0	0.0	5.01	10
105.11	50.0	39.9	0.0	0.0	0.0	0.0	0.0	9.66	6
<u>105.00</u>	<u>39.2</u>	39.2	0.0	0.0	0.0	0.0	0.0	OVERTOPPING	

Table 9. Culvert Size, Head, & Flows at Crossing #4

FHWA CULVERT ANALYSIS									
HY-8, VERSION 6.0									
C	SITE DATA			CULVERT SHAPE, MATERIAL, INLET					
U									
L	INLET	OUTLET	CULVERT	BARRELS					
V	ELEV.	ELEV.	LENGTH	SHAPE	SPAN	RISE	MANNING	INLET	
NO.	(ft)	(ft)	(ft)	MATERIAL	(ft)	(ft)	n	TYPE	
1	100.00	99.50	<u>25.00</u>	1 CSP	<u>2.25</u>	<u>2.25</u>	.024	CONVENTIONAL	
SUMMARY OF CULVERT FLOWS (cfs)									
				FILE: BUZFOUR			DATE: 01-29-2000		
ELEV (ft)	TOTAL	1	2	3	4	5	6	ROADWAY	ITR
100.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.00	1
101.11	5.0	5.0	0.0	0.0	0.0	0.0	0.0	0.00	1
101.68	10.0	10.0	0.0	0.0	0.0	0.0	0.0	0.00	1
<u>102.21</u>	<u>15.0</u>	15.0	0.0	0.0	0.0	0.0	0.0	0.00	1
102.92	20.0	20.0	0.0	0.0	0.0	0.0	0.0	0.00	1
103.55	25.0	25.0	0.0	0.0	0.0	0.0	0.0	0.00	1
104.46	30.0	30.0	0.0	0.0	0.0	0.0	0.0	0.00	1
105.04	35.0	32.7	0.0	0.0	0.0	0.0	0.0	1.97	26
105.09	40.0	32.9	0.0	0.0	0.0	0.0	0.0	6.83	8
105.12	45.0	33.1	0.0	0.0	0.0	0.0	0.0	11.57	6
105.15	50.0	33.2	0.0	0.0	0.0	0.0	0.0	16.32	5
<u>105.00</u>	<u>32.5</u>	32.5	0.0	0.0	0.0	0.0	0.0	0.0	OVERTOPPING

Texaco Exploration and Production, Inc

Area Map of Crossing #4



UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil ☒ Gas ☐

2. Name of Operator

Texaco Exploration & Production, Inc.

3. Address and Telephone No.

3300 N. Butler, Suite 100, Farmington, New Mexico 87401

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

539' FSL, 1831' FEL
SW/4 SE/4, Section 22, T18S, R7E, SLB&M

5. Lease Designation and Serial No.

UTU-68538

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA, Agreement Designation

N/A

8. Well Name and No.

Federal T 22-83

9. API Well No.

10. Field and Pool, or Exploratory Area

Undesignated

11. County or Parish, State

Emery County, Utah

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐
- Notice of Intent
-
- ☒
- Subsequent Report
-
- ☐
- Final Abandonment Notice

TYPE OF ACTION

- | | |
|---|--|
| <input type="checkbox"/> Change of Name | <input type="checkbox"/> Change of Plans |
| <input type="checkbox"/> Recompletion | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Plugging Back | <input type="checkbox"/> Non-Routine Fracturing |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Altering Casing | <input type="checkbox"/> Conversion to Injection |
| <input checked="" type="checkbox"/> Transmission Line Information | <input type="checkbox"/> Dispose Water |

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Please include the following information with the previously submitted Application for Permit to Drill (all sizes and lengths are approximate based on information available at this time):

The Gas Pipeline will be 6" to 12" in diameter, buried at a depth of 4', and travel 2,600' along the proposed access road.

The Water Pipeline will be 8" to 16" in diameter, buried at a depth of 4', and travel 2,600' within the same trench as the gas pipeline.

The 3-Phase Power Line will be overhead, opposite the pipelines, and travel 2,600' along the proposed access road.

14. I hereby certify that the foregoing is true and correct

Signed Ron With Title Prod. SUPERVISOR Date 2/14/00

(This space for Federal or State office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any:

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED

FEB 17 2000

DIVISION OF
OIL, GAS AND MINING



Texaco Exploration
and Production Inc.
Denver Region

3300 North Butler
Farmington, NM 87401
505 325-4397

January 15, 2001

Ms. Lisha Cordova
State of Utah Department of Natural Resources
Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P.O. Box 145801
Salt Lake City, Utah 84114-5801

CONFIDENTIAL

Re: **Application for Permit to Drill
Permit Extension**

WELL	APPROVED	SEC	RNGE	TWN	COUNTY	STATE
43-015-30445 26-88	2/9/00	26	18S	7E	Emery	Utah
43-015-30455 27-86	2/9/00	27	18S	7E	Emery	Utah
43-015-30452 22-83	2/9/00	22	18S	7E	Emery	Utah
43-015-30447 23-84	2/9/00	23	18S	7E	Emery	Utah
43-015-30453 22-91	2/9/00	22	18S	7E	Emery	Utah
43-015-30448 3-92	2/9/00	3	18S	7E	Emery	Utah
43-015-30449 3-93	2/9/00	3	18S	7E	Emery	Utah

Dear Ms. Cordova:

The above referenced wells received state drilling permits in February 2000. The drilling and completion of these wells did not occur and will be deferred to this year. Therefore Texaco Exploration and Production, Inc. respectfully requests a one-year drilling permit extension for the above referenced wells.

Please accept this letter as Texaco Exploration and Production Incorporated's written request for confidential treatment of all information contained in and pertaining to these permit applications, if said information is eligible for such consideration.

Thank you very much for your timely consideration of this request. Please feel free to contact Roger Johnson (Ext. 25) or myself (Ext. 11) if you have any questions.

Sincerely,

Ian M. Kephart
Ferron Production Engineer

**Approved by the
Utah Division of
Oil, Gas and Mining**
Date: 01-25-01
By: [Signature]

COPY SENT TO OPERATOR
Date: 01-25-01
Initials: CHD

RECEIVED

JAN 22 2001

DIVISION OF
OIL, GAS AND MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. TYPE OF WORK

DRILL ☒

DEEPEN ☐

b. TYPE OF WELL

OIL WELL ☐

GAS WELL ☒

OTHER ☐

SINGLE ZONE ☒

MULTIPLE ZONE ☐

2. NAME OF OPERATOR

Texaco Exploration and Production, Inc.

3. ADDRESS AND TELEPHONE NO.

3300 North Butler, Farmington, NM 87401; 505-325-4397

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*

At surface

At proposed prod. zone

539' FSL, 1831' FEL

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

3.7 miles northwest of Orangeville, Utah

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drig. unit line, if any)

1831'

16. NO. OF ACRES IN LEASE

2205.82

18. DISTANCE FROM PROPOSED
LOCATION TO NEAREST WELL,
DRILLING, COMPLETED, OR
APPLIED FOR, ON THIS LEASE, FT.

2250'

19. PROPOSED DEPTH

3435'

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

6385' GR

17. NO. OF ACRES ASSIGNED
TO THIS WELL

160 acres

20. ROTARY OR CABLE TOOLS

Rotary

22. APPROX. DATE WORK WILL START*

April 2000

23. PROPOSED CASING AND CEMENTING PROGRAM


SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8" K-55 ST&C	24	300'	230 sacks Class G cement + 2% CaCl ₂ + 0.25 pps cellophane flakes
7-7/8"	5-1/2" N-80 LT&C	17	3435'	135 sacks 10:1 RFC Class G cement + 0.25 pps cellophane flakes

Bond # CO 0058

RECEIVED

MAY 29 2001

DIVISION OF
OIL, GAS AND MINING



FLARING OR VENTING OF
GAS IS SUBJECT TO NTL 4-A
Dated 1/1/80

CONDITIONS OF APPROVAL ATTACHED

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

TITLE FARMINGTON O. U. TEAM LEADER DATE 1/7/2000

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon
CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY

/S/ WILLIAM C. STRINGER

Assistant Field Manager,
Division of Resources

DATE


MAY 23 2001

*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency or the

Township 18 South

Range 7 East



Location:

The Bearings Indicated are per the recorded plat obtained from the U.S. Land Office. The well location was determined using a Trimble 4700 GPS survey grade unit.

Basis of Elevation:


Basis of Elevation of 6006.86' being a Utah State Engineer's benchmark located between Section 25 and Section 26, T18S., R9E., Salt Lake Base & Meridian, 350' South of the Northwest Corner of Section 25, Township 18 South, Range 7 East.

Description of Location:

Proposed Drill Hole located in the SW 1/4, SE 1/4 of Section 22; being 539.0' North and 1831.1' West from the Southeast Corner of Section 22, T18S., R7E., Salt Lake Base and Meridian.

Surveyor's Certificate:

I, Albert J. Spensko, a Registered Professional Land Surveyor, holding Certificate 146652 State of Utah, do hereby certify that the information on this drawing is a true and accurate survey based on data of record and was conducted under my personal direction and supervision as shown hereon.




Talon Resources, Inc.
375 South Carbon Avenue, Suite 126
Price, Utah 84501
Ph: 435-837-5032 ext. 711
Fax: 435-748-5085

TEXACO E & P
WELL # 22-83
Section 22, T18S., R7E., S.L.B.&M.
Emery County, Utah

Drawn By: D. Robertson	Checked By: L.W.J.
Drawing No. A-1	Date: 11/19/99
	Scale: 1" = 1000'
Sheet 1 of 4	Job No. 050

GRAPHIC SCALE



Legend

- Drill Hole Location
- ⊙ Brass Cap (Found)
- Brass Cap (Searched for, but not found)
- △ Calculated Corner
- () GLO
- GPS Measured

Texaco Exploration & Production, Inc.
Federal T 22-83
Lease U-68538
SWSE Section 22, T18S, R7E
Emery County, Utah

A COMPLETE COPY OF THIS PERMIT SHALL BE KEPT ON LOCATION, from the beginning of site construction through well completion, and shall be available to contractors to ensure compliance.

CONDITIONS OF APPROVAL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be advised that Texaco Exploration & Production, Inc. is considered to be the operator of the above well and is responsible under the terms and conditions of the lease for the operations conducted on the leased lands.

Bond coverage for this well is provided by CO0058 (Principal - Texaco Exploration & Production, Inc.) via surety consent as provided for in 43 CFR § 3104.2.

This office will hold the aforementioned operator and bond liable until the provisions of 43 CFR § 3106.7-2 continuing responsibility are met.

This permit will be valid for a period of one year from the date of approval. After permit termination, a new application must be filed for approval.

All lease operations will be conducted in full compliance with applicable regulations (43 CFR § 3100), Onshore Oil and Gas Orders, lease terms, notices to lessees, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors.

A. DRILLING PROGRAM

1. The proposed BOP system is in a 2M configuration. Although components of the system are rated to 3000 psi, testing to the requirements of a 2M system will be sufficient.
2. The choke manifold schematic does not clearly depict a pressure gauge. A pressure gauge must be installed on the choke manifold (preferably at the cross), and a valve capable of isolating the gauge from manifold pressure must be in-place.
3. The requirements for air drilling, found in Onshore Oil and Gas Order No. 2, part III, E (Special Drilling Operations), shall be followed. This section requires, at a minimum, the use of the following equipment not mentioned in the application:
 - Spark arresters
 - Blooie line discharge at least 100 feet from wellbore
 - Straight blooie line
 - Deduster equipment
 - Float valve above bit
 - Automatic igniter on the blooie line
4. A cement bond log (CBL) or other appropriate tool shall be used to determine the top-of-cement behind the production casing.
5. Concurrent approval from the State of Utah, Division of Oil, Gas & Mining is required before conducting any surface disturbing activities.

SURFACE USE

1. The following appendices are attached for your reference. They are to be followed as conditions of approval:

Table A-1, Seed Mixture for Green Strip Areas

Table A-2, Seed Mixture for Final Reclamation, Pinyon-Juniper Areas

EMP 16 & 17, Winter Seasonal Restriction on Critical & High Priority Winter Range

EMP 19, Critical Winter Range Browse Hand Planting

EMP 21, Surface Disturbance Mitigation for Critical and High Priority Winter Range

2. Whether the mud pit shall be lined will be determined at the time of construction.
3. Within six months of installation, surface structures shall be painted in the following flat, earth tone color: Olive Black (5W A 20-6). This Fuller O'Brien color is for reference only. Any brand of paint may be used provided the colors match. Any facilities that must be painted to comply with OSHA standards are exempt.

GENERAL CONSTRUCTION

1. Operator shall contact the Price BLM Office at least forty-eight hours prior to the anticipated start of construction and/or any surface disturbing activities. The BLM may require and schedule a preconstruction conference with the operator prior to the operator commencing construction and/or surface disturbing activities. The operator and the operator's contractor, or agents involved with construction and/or any surface disturbing activities associated with the project, shall attend this conference to review the Conditions of Approval and plan of development. The operator's inspector will be designated at the pre-drill conference, and is to be given an approved copy of all maps, permits and conditions of approval before the start of construction. The BLM will also designate a representative for the project at the preconstruction conference.
2. The operator shall designate a representative(s) who shall have the authority to act upon and to implement instructions from the BLM. The operator's representative shall be available for communication with the BLM within a reasonable time when construction or other surface disturbing activities are underway.

3. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the operator, or any person working on his behalf, on public land is to be immediately reported to the Price BLM Office. The operator will suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Price BLM Office. An evaluation of the discovery will be made by the BLM to determine appropriate actions to prevent the loss of significant cultural or scientific values. The operator is responsible for the cost of evaluation of any site found during construction. The BLM will determine what mitigation is necessary.
4. During project construction, surface disturbance and vehicle travel shall be limited to the approved location and access routes. Any additional area needed must be approved by the Price BLM Office prior to use.
5. The operator must provide a trash cage for the collection and containment of all trash. The trash shall be disposed in an authorized landfill. The location and access roads shall be kept litter free.
6. Vegetation removal necessitated by construction shall be confined to the limits of actual construction. Removed vegetation will be stockpiled for use in reclamation or removed from the construction site at the direction of the BLM.
7. Prior to surface disturbance, topsoil is to be separately removed and segregated from other material. Topsoil depth will be decided onsite by BLM. If the topsoil is less than 6 inches, a 6-inch layer that includes the A horizon and the unconsolidated material immediately below the A horizon shall be removed and the mixture segregated and redistributed as the surface soil layer.

Generally topsoil shall be stored within the pad site or adjacent to access roads. The company in consultation with BLM shall determine stockpile locations and dimensions at the onsite. If the topsoil stockpiles will not be redistributed for a period in excess of one (1) year, the stockpiles are to be seeded with seed mixture Pinyon-Juniper (see attached).

ROAD and PIPELINE CONSTRUCTION

8. Operator shall provide an inspector under the direction of a registered professional engineer (PE) at all times during road construction. A PE shall certify (statement with PE stamp) that the road was constructed to the required Bureau of Land Management (BLM) road standards.
9. Road construction or routine maintenance activities are to be performed during periods when the soil can adequately support construction equipment. If such

equipment creates ruts more than 6 inches deep, the soil is deemed too wet to adequately support construction equipment.

10. The operator is responsible for maintenance of all roads authorized through the lease or a right-of-way. Construction and maintenance shall comply with Class II or III Road Standards as described in BLM Manual Section 9113 and the Moab District Road Standards, except as modified by BLM. Maintenance may include but is not limited to grading, applying gravel, snow removal, ditch cleaning, headcut restoration/prevention.
11. Topsoil from access roads and pipelines is to be wind rowed along the uphill side of the road or stored in an approved manner. When the road and pipeline is rehabilitated, this soil will then be used as a top coating for the seed bed.
12. Erosion-control structures such as water bars, diversion channels, and terraces will be constructed to divert water and reduce soil erosion on the disturbed area. Road ditch turnouts shall be equipped with energy dissipaters as needed to avoid erosion. Where roads interrupt overland sheet-flow and convert this runoff to channel flow, ditch turnouts shall be designed to reconvert channel flow to sheet flow. Rock energy dissipaters and gravel dispersion fans may be used, or any other design which would accomplish the desired reconversion of flow regime. As necessary cut banks, road drainage, and road crossings shall be armored or otherwise engineered to prevent head-cutting.
13. This permit will not cover electric power to the wells. A separate permit will be required when Texaco is sure of its plans.

PAD CONSTRUCTION

14. During the construction of the drill pad, suitable topsoil material is to be stripped and conserved in a stockpile on the pad. If stockpiles are to remain for more than a year, they shall be seeded with the seed mixture Pinyon-Juniper (see attached).
15. Generally, drill pads are to be designed to prevent overland flow of water from entering or leaving the site. The pad is to be sloped to drain spills and water into the reserve pit. The drill pad shall be designed to disperse diverted overland flow and to regulate flow velocity so as to prevent or minimize erosion. Well pad diversion outlets shall be equipped with rock energy brakes and gravel-bedded dispersion fans.

REHABILITATION PROCEDURES

Site Preparation

16. The entire roadbed should be obliterated and brought back to the approximate original contour. Drainage control is to be reestablished as necessary. All areas affected by road construction are to be recontoured to blend in with the existing topography. All berms are to be removed unless determined to be beneficial by BLM. In recontouring the disturbed areas, care should be taken to not disturb additional vegetation.

Seedbed Preparation

17. An adequate seedbed should be prepared for all sites to be seeded. Areas to be revegetated should be chiseled or disked to a depth of at least 12 inches unless restrained by bedrock.
18. Ripping of fill materials should be completed by a bulldozer equipped with single or a twin set of ripper shanks. Ripping should be done on 4-foot centers to a depth of 12 inches. The process should be repeated until the compacted area is loose and friable, then shall be followed by final grading. Seedbed preparation will be considered complete when the soil surface is completely roughened and the number of rocks (if present) on the site is sufficient to cause the site to match the surrounding terrain.
19. After final grading, the stockpiled topsoil shall be spread evenly across the disturbed area.

Fertilization

20. Commercial fertilizer with a formula of 16-16-8 is to be applied at a rate of 200 pounds per acre to the site. The rate may be adjusted depending on soil.
21. Fertilizer is to be applied not more than 48 hours before seeding, and shall be cultivated into the upper 3 inches of soil.
22. Fertilizer is to be broadcast over the soil using hand-operated "cyclone-type" seeders or rotary broadcast equipment attached to construction or revegetation machinery as appropriate to slope. All equipment should be equipped with a metering device. Fertilizer application is to take place before the final seeding.

preparation treatment. Fertilizer broadcasting operations should not be conducted when wind velocities would interfere with even distribution of the material.

Mulching

23. When it is time to reclaim this location, the Price BLM Office will determine whether it will be necessary to use mulch in the reclamation process. The type of mulch should meet the following requirements: Wood cellulose fiber shall be natural or cooked, shall disperse readily in water, and shall be nontoxic. Mulch shall be thermally produced and air dried. The homogeneous slurry or mixture shall be capable of application with power spray equipment. A colored dye that is noninjurious to plant growth may be used when specified. Wood cellulose fiber is to be packaged in new, labeled containers. A minimum application of 1500 pounds per acre shall be applied. A suitable tackifier shall be applied with the mulch at a rate of 60 to 80 pounds per acre.

An alternative method of mulching on small sites would be the application of straw or hay mulch at a rate of 2000 pounds per acre. Hay or straw shall be certified weed free. Following the application of straw or hay, crimping shall occur to ensure retention.

Reseeding

24. All disturbed areas are to be seeded with the seed mixture required by the BLM. The seed mixture(s) shall be planted in the fall of the year (Sept-Nov), in the amounts specified in pounds of pure live seed (PLS)/acre. There shall be no noxious weed seed in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within 12 months prior to planting. Commercial seed will be either certified or registered seed. The seed mixture container shall be tagged in accordance with State law(s) and available for inspection by the BLM. Seed is to be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture shall be evenly and uniformly planted over the disturbed area. (Smaller/heavier seeds tend to drop to the bottom of the drill and are planted first. Appropriate measures should be taken to ensure this does not occur.) Where drilling is not possible, seed is to be broadcast and the area raked or chained to cover the seed. Woody species with seeds that are too large for the drill will be broadcast. When broadcasting the seed, the pounds per acre noted below are to be increased by 50 percent. Reseeding may be required if a satisfactory stand is not established to the surface rights owner's specifications. Evaluation of the seeding's success will not be made before completion of the second growing season after the

vegetation becomes established. The Price BLM Office is to be notified a minimum of seven days before seeding a project.

25. The disturbed areas for the road and pipeline must be seeded in the fall of the year, immediately after the topsoil is replaced. The prescribed seed mixture is Pinyon-Juniper (see attached).

General

26. Prior to the use of insecticides, herbicides, fungicides, rodenticides and other similar substances, the operator must obtain from BLM, approval of a written plan. The plan must describe the type and quantity of material to be used, the pest to be controlled, the method of application, the location for storage and disposal of containers, and other information that BLM may require. A pesticide may be used only in accordance with its registered uses and within other agency limitations. Pesticides must not be permanently stored on public lands.

The following seed mixture would be planted along service road borrow ditches, around the edges of drill pads with a production well, and surrounding other production and maintenance facilities. The purpose for this is to provide a "green strip" buffer to minimize fire hazards and prevent invasion and establishment of noxious weeds in areas that will receive continued disturbance for the life of these areas.

Table A-1

Common Plant Name	Scientific Name	Pounds per acre (PLS)
Forage kochia	<i>Kochia prostrata</i>	2
Wyoming big sagebrush	<i>Artemisia tridentata wyomingensis</i> var. Gordon Creek	1
Douglas low rabbitbrush	<i>Chrysothamnus viscidiflorus</i>	1
TOTAL		4

The following seed mixture is for the area that would receive final reclamation. Areas would be planted to protect them from soil erosion and to restore forage production.

Table A-2

Common Plant Name	Scientific Name	Pounds per acre (PLS) ¹
Pinyon Juniper Areas		
<i>Grasses</i>		
Thickspike wheatgrass	<i>Elymus lanceolatus</i>	1.5
Intermediate wheatgrass	<i>Elytrigia intermedia</i>	1.5
Squirreltail	<i>Elymus elymoides</i>	2
Crested wheatgrass	<i>Agropyron desertorum</i>	2
<i>Forbs</i>		
Lewis flax	<i>Linum perenne lewisii</i>	1
Palmer penstemon	<i>Penstemon palmerii</i>	1
<i>Shrubs</i>		
Forage kochia	<i>Kochia prostrata</i>	2
Fourwing saltbrush	<i>Atriplex canescense</i>	2
Wyoming big sagebrush	<i>Artemesia tridentata wyomingensis</i>	1
	var. Gordon Creek	
Antelope bitterbrush	<i>Purshia tridentata</i>	1
TOTAL		15

1. Seeding rate is listed as pounds per acre of pure live seed (PLS) drilled. Rate is increased by 50 percent if broadcast seeded.

Formula: pure live seed (PLS) = % seed purity x % seed germination

FERRON NATURAL GAS PROJECT AREA

PROPONENT: _____ **WELL #:** 22-83

EPM 16 & 17: WINTER SEASONAL RESTRICTION (DECEMBER 1 to APRIL 15) ON CRUCIAL AND HIGH PRIORITY WINTER RANGE.

Pg 1 of 1

Restrictions on Construction Phase Activity: Prohibit construction phase activity, described below, on big game high value and critical winter range during the period (December 1 - April 15) without regard for land ownership.

This condition would not apply to normal maintenance and operation of producing wells, described below. On nonfederal lands (where the federal government does not have either surface or subsurface ownership) the Companies would be allowed to conduct construction phase activity if needed to avoid breach of contract or loss of lease rights. In the event construction phase activity proceeds into the winter closure period on non federal interest lands, Companies would make available appropriate documentation to UDWR, upon request.

Construction Phase Activity: Construction phase activity is considered to include all work associated with initial drilling and construction of facilities through completion, including installation of pumping equipment, connection with ancillary facilities and tie-in with pipelines necessary for product delivery.

Companies would not be allowed to initiate construction activity unless it is reasonable to believe that such work can be finished to a logical stopping point prior to December 1 of that year. Specific activities considered to be covered by the seasonal closure include all heavy equipment operation including but not limited to the following:

- Mobilization/Demobilization or operation of heavy equipment (crawler tractor, front end loader, backhoe, road grader, etc.)
- Construction activity (road construction or upgrading, pad, pipeline, powerline, ancillary facilities, etc.),
- Drilling activity (Operator would not propose or initiate drilling activity if the project could not reasonably be expected to be finished to a logical stopping point by the December 1 date of that year.)
- Seismic operation, detonation of explosives

This seasonal closure would not apply to reconnaissance, survey/design and/or flagging of project work or other similar activity not requiring actions listed for heavy equipment operation.

Production Phase: A well is considered to be in production phase when the well and ancillary facilities are completed to the point that they are capable of producing and delivering product for sale. It is noted that heavy equipment operation may be necessary in the performance of maintenance and operation of producing wells.

Restriction on Non Emergency Workover Operations: The Companies will schedule non-emergency workover operations (defined below) on big game crucial and high value winter range outside the December 1 to April 15 date of the seasonal closure.

Non-emergency Workover Operations: Workover operations to correct or reverse a gradual loss of production over time (loss of production of 20 percent or less over a 60 day period) is considered to be routine or non-emergency workover operations and would not be permitted during the December 1 to April 15 time frame.

Emergency Workover Operations: Emergency work over operations are defined as downhole equipment failure problems or workover operation necessary to avoid shut in of the well or to avoid an immediate safety or environmental problem. Loss of production greater than 20 percent within a 60 day period is indicative of pump failure and will be treated as an emergency workover operation. The Companies will submit Sundry notices to BLM within five days of the emergency workover operations between December 1 and April 15.

FERRON NATURAL GAS PROJECT AREAPROPOSER: _____ WELL #: 22-83**EPM 19: CRITICAL WINTER RANGE BROWSE HAND PLANTING**

Pg 1 of 1

One or two browse species lists (checked below) are to be hand planted at the prescribed application rate and according to the following prescribed methods on critical winter range areas that are undergoing long term reclamation. This would include all pipeline corridors, berm around edge of drill pads, miscellaneous disturbed areas associated with construction such as staging areas for equipment, sidecast on road cuts, along side upgraded or new roads up to and including borrow ditch and in the termination of redundant access roads being closed. This planting shall be completed in the first planting window following reclamation.

Planting Methods:

Planting shall be accomplished using a labor force with specific experience in landscape restoration, hand planting methods and handling and care of browse tubling and or bareroot stock plants.

Browse plants to be utilized can be bareroot stock or tubling stock plants of 1 year old age class or greater.

Browse seedling protectors will be used to provided protection from browsing ungulates for two years. Seedling protectors will be of an open mesh rigid design that will break down when exposed to sunlight and that measures a minimum of 12 inches in length and 4 inches in diameter. The protectors will be secured around the browse seedlings.

Planting shall be completed in the spring (March 1- April 1) and or fall (November 1- December 1) planting windows.

Browse plants shall be stored and handled in such a manner as to maintain viability, according to the type of browse stock being used.

Planting Species and Application Rate:

<u>Species</u>	<input checked="" type="checkbox"/> Sagebrush-Grass <u>Plants Per Acre</u>	<input type="checkbox"/> Pinyon-Juniper
Wyoming Sagebrush (Gordon Creek)	100	50
Fourwing Saltbush (Utah seed source collected at or above 5,000 feet elevation)	100	50
True Mountain Mahogany (Utah seed source)	0	50
Antelope Bitterbrush (Utah seed source)	0	50
Total	200	200

Suitable Substitutions:

Prostrate Kochia	yes	yes
Whitestem Rubber Rabbitbrush	no	yes
Utah Serviceberry	no	yes
Winterfat	yes	no

FERRON NATURAL GAS PROJECT AREA

PROPONENT: _____ **WELL #:** 22-83

EPM 21: SURFACE DISTURBANCE MITIGATION FOR CRITICAL AND HIGH PRIORITY WINTER RANGE

Pg. 1 of 1

The subject permit application is proposed within critical and high priority winter range (FEIS) and subject to EPM 21 requiring acre for acre mitigation for surface disturbance on critical winter range. The following condition comes from a cooperative agreement between the Texaco, Anadarko, Chandler (Companies), BLM-Price Field Office, the Utah Division of Wildlife Resources and the National Fish and Wildlife Foundation. The Companies agreed to the following:

1. Contribute \$1,301.26 (1998 dollars) for each Federal interest well (Federal surface and or subsurface ownership) permitted and drilled by the Companies (or on behalf of Companies by its contractor) on big game critical winter range as depicted in the FEIS Ferron Natural Gas Project Area. (Wells meeting the above criteria for which payment will be required, will be referred to as "subject wells".) This contribution will be adjusted annually for inflation based on the Consumer Price Index (CPI), see Section II.C.6. for the reference source used for the determination of the CPI and the date in which this annual adjustment will go into effect.

Since this mitigation program is designed to address impacts of all big game critical winter range surface disturbance (roads, well pads, pipelines, etc.), contributions will be required regardless of the success or failure of the subject well to produce.

- a. The recorded date for spudding for each subject well (the first boring of a hole during the drilling of a well) will serve as the reference date triggering the requirement for the mitigation contribution.
- b. Contributions will be submitted (in the form of an Company check, cashiers check or wire transfer) directly to the National Fish and Wildlife Foundation by the 1st of August and February for all subject wells spudded in the preceding six months as reported by the Bureau.
- c. All contributions will be made payable to the "National Fish and Wildlife Foundation re, Proj 99-270" and reference the "Ferron Natural Gas Wildlife Habitat Impact Mitigation Fund".

C. REQUIRED APPROVALS, REPORTS AND NOTIFICATIONS

Required verbal notifications are summarized in Table 1, attached.

Building Location- Contact the BLM Natural Resource Protection Specialist at least 48-hours prior to commencing construction of location.

Spud- The spud date will be reported to BLM 24-hours prior to spudding. Written notification in the form of a Sundry Notice (Form 3160-5) will be submitted to the Moab Field Office within 24-hours after spudding, regardless of whether spud was made with a dry hole digger or big rig.

Daily Drilling Reports- Daily drilling reports shall detail the progress and status of the well and shall be submitted to the Moab Field Office on a weekly basis.

Monthly Reports of Operations- In accordance with Onshore Oil and Gas Order No. 1, this well shall be reported on Minerals Management Service (MMS) Form 3160, "Monthly Report of Operations," starting the month in which operations commence and continuing each month until the well is physically plugged and abandoned. This report will be filed directly with MMS.

Sundry Notices- There will be no deviation from the proposed drilling and/or workover program without prior approval. "Sundry Notices and Reports on Wells" (Form 3160-5) will be filed, with the Moab Field Office, for approval of all changes of plans and subsequent operations in accordance with 43 CFR § 3162.3-2. Safe drilling and operating practices must be observed.

Drilling Suspensions- Operations authorized by this permit shall not be suspended for more than 30 days without prior approval of the Moab Field Office. All conditions of this approval shall be applicable during any operations conducted with a replacement rig.

Undesirable Events- Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be immediately reported to the BLM in accordance with requirements of NTL-3A.

Cultural Resources- If cultural resources are discovered during construction, work that might disturb the resources is to stop, and the Price Field Office is to be notified.

First Production- Should the well be successfully completed for production, the Moab Field Office will be notified when the well is placed in producing status. Such notification may be made by phone, but must be followed by a sundry notice or letter not later than five business days following the date on which the well is placed into production.

A first production conference will be scheduled as soon as the productivity of the well is apparent. This conference should be coordinated through the Price Field Office. The Price Field Office shall be notified prior to the first sale.

Well Completion Report- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted to the Moab Field Office not later than thirty-days after completion of the well or after completion of operations being performed, in accordance with 43 CFR § 3162.4-1. Two copies of all logs, core descriptions, core analyses, well test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. When requested, samples (cuttings and/or samples) will be submitted to the Moab Field Office.

Venting/Flaring of Gas- Gas produced from this well may not be vented/flared beyond an initial, authorized test period of 30 days or 50 MMcf, whichever first occurs, without the prior, written approval of the Moab Field Office. Should gas be vented or flared without approval beyond the authorized test period, the well may be ordered shut-in until the gas can be captured or approval to continue the venting/flaring as uneconomic is granted. In such case, compensation to the lessor shall be required for that portion of the gas that is vented/flared without approval and which is determined to have been avoidably lost.

Produced Water- An application for approval of a permanent disposal method and location will be submitted to the Moab Field Office for approval pursuant to Onshore Oil and Gas Order 7.

Off-Lease Measurement, Storage, Commingling- Prior approval must be obtained from the Moab Field Office for off-lease measurement, off-lease storage and/or commingling (either down-hole or at the surface).

Plugging and Abandonment- If the well is completed as a dry hole, plugging instructions must be obtained from the Moab Field Office prior to initiating plugging operations.

A "Subsequent Report of Abandonment" (Form 3160-5) will be filed with the Moab Field Office within thirty-days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Upon completion of approved plugging, a regulation marker will be erected in accordance with 43 CFR § 3162.6. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the Price Field Office or the appropriate surface managing agency.

TABLE 1

NOTIFICATIONS

Notify Mike Kaminski (work: 435-636-3640, home: 435-637-2518)
or Don Stephens (work: 435-636-3608, home: 435-637-7967)
of the BLM, Price Field Office for the following:

2 days prior to commencement of dirt work, construction and reclamation;

1 day prior to spudding;

50 feet prior to reaching the surface casing setting depth

If the people above cannot be reached, notify the Moab Field Office at (435) 259-2100. If unsuccessful, contact the person listed below.

Well abandonment operations require 24 hour advance notice and prior approval. In the case of newly drilled dry holes, verbal approval can be obtained by calling the Moab Field Office at (435) 259-2100. If approval is needed after work hours, you may contact the following:

Eric Jones, Petroleum Engineer	Office: (435) 259-2117
	Home: (435) 259-2214

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>Operator Name Change</u>		5. LEASE DESIGNATION AND SERIAL NUMBER: See Attached List of Wells
2. NAME OF OPERATOR: Chevron U.S.A. Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: BLM & State of Utah
3. ADDRESS OF OPERATOR: P.O. Box 36366 CITY Houston STATE TX ZIP 77236		7. UNIT or CA AGREEMENT NAME: Orangeville & Huntington
PHONE NUMBER: (281) 561-3443		8. WELL NAME and NUMBER: See Attached List of Wells
4. LOCATION OF WELL FOOTAGES AT SURFACE: See Attached List of Wells		9. API NUMBER:
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		10. FIELD AND POOL, OR WILDCAT:

COUNTY: Emery

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input checked="" type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input type="checkbox"/> OTHER: <u>Operator Name Change (Merger)</u>
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective May 1, 2002, Chevron U.S.A. Inc. is the new operator of the attached list of subject wells and leases that were previously operated by Texaco Exploration and Production Inc. The subject wells are located North of Orangeville and North of Huntington, Emery County, Utah. These Wells will be protected by the following surety bonds:

STATE OF UTAH Bond #: 103521627-0016 in the amount of \$80,000. (This bond will replace United Pacific Insurance Company bond number U89-75-80-0059. We respectfully request this bond be released and returned.)

BLM Nationwide Bond#: U89-75-81-0034 in the amount of \$300,000.

Key Contacts:

Ron Wirth - Operations Supervisor - 435 748-5395 x1
Texaco Exploration & Production Inc.

J. S. Purdy, Attorney-In-Fact

RECEIVED

MAY 06 2002

DIVISION OF
OIL, GAS AND MINING

NAME (PLEASE PRINT) Allen S. Robinson

TITLE Attorney-In-Fact

SIGNATURE Allen S. Robinson

DATE April 30, 2002

(This space for State use only)

Chevron U.S.A. Inc.
Midcontinent Business Unit
Ferron Operations
Emery County, Utah

Name / Operatorship Change
Texaco Exploration and Production Inc.
to
Chevron U.S.A. Inc.

Account Number	Section	Township	Range	API Number	Well Name	Lease Type	Well Status Main	Well Type Main	Fed or State
N5700	06	170S	080E	4301530292	UTAH FEDERAL M 6-25	1	S	GW	Federal
N5700	34	170S	070E	4301530282	UTAH FEDERAL D 34-12	1	P	GW	Federal
N5700	34	170S	070E	4301530389	USA 34-80	1	P	GW	Federal
N5700	34	170S	070E	4301530390	USA 34-82	1	P	GW	Federal
N5700	35	170S	070E	4301530285	UTAH FEDERAL D 35-13	1	P	GW	Federal
N5700	35	170S	070E	4301530286	UTAH FEDERAL D 35-14	1	P	GW	Federal
N5700	35	170S	070E	4301530287	UTAH FEDERAL D 35-15	1	P	GW	Federal
N5700	03	180S	070E	4301530383	USA 3-74	1	P	GW	Federal
N5700	03	180S	070E	4301530384	USA 3-75	1	P	GW	Federal
N5700	03	180S	070E	4301530448	FEDERAL P 3-92	1	DRL	GW	Federal
N5700	03	180S	070E	4301530449	FEDERAL P 3-93	1	DRL	GW	Federal
N5700	04	180S	070E	4301530280	UTAH FEDERAL Q 4-44	1	P	GW	Federal
N5700	08	180S	070E	4301530274	UTAH FEDERAL S 8-46	1	P	GW	Federal
N5700	10	180S	070E	4301530258	UTAH FEDERAL P 10-47	1	P	GW	Federal
N5700	10	180S	070E	4301530276	UTAH FEDERAL P 10-42	1	P	GW	Federal
N5700	10	180S	070E	4301530277	UTAH FEDERAL P 10-43	1	P	GW	Federal
N5700	11	180S	070E	4301530385	USA 11-70	1	APD	GW	Federal
N5700	11	180S	070E	4301530386	USA 11-71	1	APD	GW	Federal
N5700	11	180S	070E	4301530387	USA 11-72	1	P	GW	Federal
N5700	11	180S	070E	4301530388	USA 11-73	1	APD	GW	Federal
N5700	21	180S	070E	4301530450	FEDERAL T 21-94	1	APD	GW	Federal
N5700	22	180S	070E	4301530451	FEDERAL T 22-69	1	P	GW	Federal
N5700	22	180S	070E	4301530452	FEDERAL T 22-83	1	APD	GW	Federal
N5700	22	180S	070E	4301530453	FEDERAL T 22-91	1	APD	GW	Federal
N5700	23	180S	070E	4301530245	FEDERAL C23-8	1	P	GW	Federal
N5700	23	180S	070E	4301530447	FEDERAL C 23-84	1	APD	GW	Federal
N5700	26	180S	070E	4301530244	FEDERAL A26-2	1	P	GW	Federal
N5700	26	180S	070E	4301530246	FEDERAL A26-4	1	P	GW	Federal
N5700	26	180S	070E	4301530445	FEDERAL A 26-88	1	APD	GW	Federal
N5700	27	180S	070E	4301530440	FEDERAL T 27-85	1	APD	GW	Federal
N5700	27	180S	070E	4301530455	FEDERAL T 27-86	1	APD	GW	Federal
N5700	27	180S	070E	4301530456	FEDERAL T 27-87	1	P	GW	Federal

6/6/03 . need to move them

TALON RESOURCES INC

CONFIDENTIAL

March 11, 2003

Mrs. Diana Mason
State of Utah
Division of Oil Gas and Mining
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RE: Request for Permit Extension — Texaco Exploration and Production Inc.

Dear Mrs. Mason:

On behalf of Texaco Exploration and Production, Inc. (Texaco) Talon Resources, Inc. respectfully submits this request for permit extension for the following wells. A one year extension will allow Texaco to construct, drill and complete the wells.

Federal A 26-88 (43-015-30445) SW/4 NW/4, Section 26, T18S, R7E, SLB&M, Emery County, Utah
Federal T 27-86 (43-015-30455) SE/4 NE/4, Section 27, T18S, R7E, SLB&M, Emery County, Utah
Federal T 22-83 (43-015-30452) SW/4 SE/4, Section 22, T18S, R7E, SLB&M, Emery County, Utah
Federal T 22-91 (43-015-30453) NE/4 NW/4, Section 22, T18S, R7E, SLB&M, Emery County, Utah
Federal C 23-84 (43-015-30447) NE/4 SW/4, Section 23, T18S, R7E, SLB&M, Emery County, Utah

Thank you for your timely consideration our previous applications. Please feel free to contact myself or Mr. Ron Wirth with Chevron at 435-748-5395 if you have any questions or need additional information.

Sincerely,

Don Hamilton
Don Hamilton
Agent for Chevron

cc: Mr. Ron Wirth, Chevron
Mr. Ken Jackson, Chevron
Chevron Well File

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 03-12-03

By: *[Signature]*

COPY SENT TO OPERATOR

Date: 03-13-03

Initials: CHD

RECEIVED

MAR 11 2003

DIV. OF OIL GAS & MINING

P.O. # 1230
(435) 687-5310

195 N. 100 West
(435) 687-5311

Huntington, Utah 84528
talon@crv.net

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH

2. CDW

3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

X Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective:

05/01/2002

FROM: (Old Operator):

TEXACO EXPLORATION & PRODUCTION, INC
11111 S. WILCREST
HOUSTON, TX 77099

Phone: (281) 561-4991

Account No. N5700

TO: (New Operator):

CHEVRON U.S.A., INC.
11111 S. WILCREST
HOUSTON, TX 77099

Phone: (281) 561-4991

Account No. N0210

CA No.

Unit:

WELL(S)

NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
USA 11-70	11	180S	070E	4301530385		Federal	GW	APD
USA 11-71	11	180S	070E	4301530386		Federal	GW	APD
UT FED P 12-153	12	180S	070E	4301530551		Federal	GW	APD
FEDERAL T 21-94	21	180S	070E	4301530450		Federal	GW	APD
FEDERAL T 22-83	22	180S	070E	4301530452		Federal	GW	APD
FEDERAL T 22-91	22	180S	070E	4301530453		Federal	GW	APD
FEDERAL C 23-84	23	180S	070E	4301530447		Federal	GW	APD
FEDERAL A 26-88	26	180S	070E	4301530445		Federal	GW	APD
FEDERAL T 27-85	27	180S	070E	4301530440		Federal	GW	APD
FEDERAL T 27-86	27	180S	070E	4301530455		Federal	GW	APD
FEDERAL T 27-90	27	180S	070E	4301530457		Federal	GW	APD

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 07/14/2003
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 07/14/2003
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 07/15/2003
- Is the new operator registered in the State of Utah: YES Business Number: 564408-0143
- If **NO**, the operator was contacted on: _____
- (R649-9-2) Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: not given

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: n/a

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: n/a

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 07/15/2003

2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 07/15/2003

3. Bond information entered in RBDMS on: n/a

4. Fee wells attached to bond in RBDMS on: n/a

STATE WELL(S) BOND VERIFICATION:

1. State well(s) covered by Bond Number: n/a

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: ES0022 *United Pacific (NR-5 rating)

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: n/a

FEE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number n/a

2. The **FORMER** operator has requested a release of liability from their bond on: n/a

The Division sent response by letter on: n/a

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:



TALON RESOURCES INC

February 17, 2004

CONFIDENTIAL

Ms. Diana Whitney
State of Utah
Division of Oil Gas and Mining
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RE: Request for Permit Extension----- Chevron USA


Dear Ms. Whitney:

On behalf of Chevron USA, Talon Resources, Inc. respectfully submits these requests for permit extension for the following wells. These extensions will allow Chevron USA time to construct, drill, and complete these wells.

Utah Federal P 12-153 (43-015-30551) NW/4NW/4, Section 12, T18S, R7E SLB&M, Emery County, Utah
Federal T 22-83 (43-015-30452) SW/4SE/4 Section 22, T18S, R7E, SLB&M, Emery County, Utah
Federal T 22-91 (43-015-30453) NE/4NW/4 Section 22, T18S, R7E, SLB&M, Emery County, Utah
Federal C 23-84 (43-015-30447) NE/4SW/4 Section 23, T18S, R7E, SLB&M, Emery County, Utah
Federal T 26-88 (43-015-30445) SW/4NW/4 Section 26, T18S, R7E, SLB&M, Emery County, Utah
Federal T 27-86 (43-015-30455) SE/4NE/4 Section 27, T18S, R7E, SLB&M, Emery County, Utah
Federal T 27-90 (43-015-30457) NW/4SW/4 Section 27, T18S, R7E, SLB&M, Emery County, Utah
State of Utah QQ 31-202D (43-015-30608) SE/4SW/4 Section 31, T16S, R8E, SLB&M, Emery Cty, Utah
State of Utah QQ 31-203D (43-015-30607) SE/4SW/4 Section 31, T16S, R8E, SLB&M, Emery Cty, Utah
State of Utah QQ 31-204D (43-015-30606) SE/4SW/4 Section 31, T16S, R8E, SLB&M, Emery Cty, Utah
State of Utah KK 32-144 (43-015-30567) SW/4SW/4 Section 32, T16S, R8E, SLB&M, Emery Cty, Utah
State Of Utah KK 32-145 (43-015-30566) NE/4SE/4 Section 32, T16S, R8E, SLB&M, Emery Dty, Utah

Please feel free to contact me at 435-687-5310 or Mr. Ron Wirth with Chevron USA at 435-748-5395 if you have any questions or concerns.

Sincerely,


Larry W. Johnson
Talon Resources, Inc.

cc: File
Mr. Ken Jackson
Mr. Ron Wirth

Chevron USA
Chevron USA

RECEIVED
FEB 19 2004
DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-68538
2. NAME OF OPERATOR: Chevron USA, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: P.O. Box 618 CITY Orangeville STATE UT ZIP 84537		7. UNIT or CA AGREEMENT NAME: N/A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 539' FSL, 1831' FEL		8. WELL NAME and NUMBER: Federal "T" 22-83
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 22 18S 7E S		9. API NUMBER: 4301530452
COUNTY: Emery		10. FIELD AND POOL, OR WILDCAT: Undesignated
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Extend State Permit
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Chevron USA Inc.
~~Texaco Exploration and Production, Inc.~~ hereby requests a one year extension of the state permit for the Federal T 22-83

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 02-23-04
By: [Signature]

COPY SENT TO OPERATOR

Date: 02-26-04
Initials: [Signature]

NAME (PLEASE PRINT) Larry Johnson

TITLE Chevron USA, Inc.

SIGNATURE

DATE 2/17/2004

(This space for State use only)

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 4301530452
Well Name: Federal "T" 22-83
Location: SW/4 SE/4, Section 22, T18S, R7E, SLB&M
Company Permit Issued to: Chevron USA, Inc.
Date Original Permit Issued: 2/9/2000

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☒

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒


Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐


Signature

2/17/2004

Date

Title: Agent for Chevron USA, Inc.

Representing: Chevron USA, Inc.

RECEIVED
FEB 19 2004
DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: Various Leases
2. NAME OF OPERATOR: XTO ENERGY INC. N2615		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Bldg K, Suite Farmington CITY STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		8. WELL NAME and NUMBER: See attached list
PHONE NUMBER: (505) 324-1090		9. API NUMBER: Multiple
		10. FIELD AND POOL, OR WILDCAT: Buzzard Bench
		COUNTY: Emery
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective August 1, 2004, the operator changed from Chevron U.S.A. Inc. to XTO ENERGY INC. for all wells on the attached list.

BLM #579173

State and Fee Bond #104312762

Kenneth W. Jackson

Kenneth W. Jackson Regulatory Specialist ChevronTexaco for Chevron U.S.A. Inc. N0210

NAME (PLEASE PRINT) <i>James L. Death</i>	TITLE <i>Vice President-Land</i>
SIGNATURE <i>James L. Death</i>	DATE <i>8/16/04</i>

(This space for State use only)

APPROVED *9/30/2004*

Earlene Russell

Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(5/2000)

(See Instructions on Reverse Side)

RECEIVED

SEP 28 2004

DIV. OF OIL, GAS & MINING

API Well Number	Well Name	Well Type	County Name	Qtr/Qtr	Section	Twn-Rng
43-015-30242-00-00	L M LEMMON 10-1	Gas Well	EMERY	SESE	10	17S-8E
43-015-30243-00-00	FEDERAL B21-3	Gas Well	EMERY	NESW	21	19S-7E
43-015-30244-00-00	FEDERAL A26-2	Gas Well	EMERY	SESW	26	18S-7E
43-015-30245-00-00	FEDERAL C23-8	Gas Well	EMERY	NENW	23	18S-7E
43-015-30246-00-00	FEDERAL A26-4	Gas Well	EMERY	SWSE	26	18S-7E
43-015-30247-00-00	FEDERAL A35-6	Gas Well	EMERY	NWNW	35	18S-7E
43-015-30248-00-00	FEDERAL A35-5	Gas Well	EMERY	NWNE	35	18S-7E
43-015-30249-00-00	FEDERAL A34-7	Gas Well	EMERY	NENE	34	18S-7E
43-015-30258-00-00	UTAH FED P 10-47	Gas Well	EMERY	NWNW	10	18S-7E
43-015-30259-00-00	A L JENSEN 27-9	Gas Well	EMERY	SESE	27	21S-6E
43-015-30268-00-00	ST OF UT T 36-10	Gas Well	EMERY	SWNE	36	16S-7E
43-015-30270-00-00	ST OF UT U 2-11	Gas Well	EMERY	NWNW	2	18S-7E
43-015-30272-00-00	SWD 1	Water Disposal Well	EMERY	SWNW	24	18S-7E
43-015-30274-00-00	UTAH FED S 8-46	Gas Well	EMERY	SESW	8	18S-7E
43-015-30275-00-00	UTAH FED R 9-45	Gas Well	EMERY	NWNE	9	18S-7E
43-015-30276-00-00	UTAH FED P 10-42	Gas Well	EMERY	NWNE	10	18S-7E
43-015-30277-00-00	UTAH FED P 10-43	Gas Well	EMERY	NWSE	10	18S-7E
43-015-30280-00-00	UTAH FED Q 4-44	Gas Well	EMERY	SESE	4	18S-7E
43-015-30282-00-00	UTAH FED D 34-12	Gas Well	EMERY	SESE	34	17S-7E
43-015-30285-00-00	UTAH FED D 35-13	Gas Well	EMERY	SWSW	35	17S-7E
43-015-30286-00-00	UTAH FED D 35-14	Gas Well	EMERY	NWNW	35	17S-7E
43-015-30287-00-00	UTAH FED D 35-15	Gas Well	EMERY	SWSE	35	17S-7E
43-015-30292-00-00	UTAH FED M 6-25	Gas Well	EMERY	SENE	6	17S-8E
43-015-30294-00-00	UTAH FED H 6-21	Gas Well	EMERY	SESW	6	20S-7E
43-015-30303-00-00	SWD 3	Water Disposal Well	EMERY	SENE	11	18S-7E
43-015-30306-00-00	ST OF UT U 2-48	Gas Well	EMERY	NWNE	2	18S-7E
43-015-30308-00-00	ST OF UT U 2-50	Gas Well	EMERY	NESW	2	18S-7E
43-015-30309-00-00	ST OF UT U 2-49	Gas Well	EMERY	NWSE	2	18S-7E
43-015-30310-00-00	L & M CURTIS 10-58	Gas Well	EMERY	SWSW	10	18S-7E
43-015-30311-00-00	ST OF UT X 16-66	Gas Well	EMERY	SENW	16	18S-7E
43-015-30312-00-00	ST OF UT X 16-65	Gas Well	EMERY	NWNE	16	18S-7E
43-015-30313-00-00	U P & L 14-53	Gas Well	EMERY	SESE	14	18S-7E
43-015-30314-00-00	U P & L 14-55	Gas Well	EMERY	NWNW	14	18S-7E
43-015-30315-00-00	U P & L 23-51	Gas Well	EMERY	SENE	23	18S-7E
43-015-30316-00-00	U P & L 24-57	Gas Well	EMERY	NWNW	24	18S-7E
43-015-30318-00-00	D & A JONES 15-68	Gas Well	EMERY	NENW	15	18S-7E
43-015-30319-00-00	D&D CURTIS 14-54	Gas Well	EMERY	SENE	14	18S-7E
43-015-30320-00-00	P & K PEACOCK 8-62	Gas Well	EMERY	SWNE	8	18S-7E
43-015-30321-00-00	PEACOCK TRUST 9-60	Gas Well	EMERY	NWSW	9	18S-7E
43-015-30323-00-00	SWD 2	Water Disposal Well	EMERY	NWNW	14	18S-7E
43-015-30324-00-00	R G NORRIS 14-40	Gas Well	EMERY	NESW	14	18S-7E
43-015-30325-00-00	L & M CURTIS 15-67	Gas Well	EMERY	NENE	15	18S-7E
43-015-30326-00-00	PEACOCK TRUST 8-61	Gas Well	EMERY	NESE	8	18S-7E
43-015-30327-00-00	PEACOCK 7-64	Gas Well	EMERY	NENE	7	18S-7E
43-015-30328-00-00	PEACOCK TRUST 8-63	Gas Well	EMERY	SENW	8	18S-7E
43-015-30329-00-00	D & A JONES 9-59	Gas Well	EMERY	SESE	9	18S-7E
43-015-30381-00-00	UTAH STATE 1-76	Gas Well	EMERY	NWNW	1	18S-7E
43-015-30382-00-00	UTAH STATE 36-78	Gas Well	EMERY	SWSW	36	17S-7E
43-015-30383-00-00	USA 3-74	Gas Well	EMERY	SESE	3	18S-7E
43-015-30384-00-00	USA 3-75	Gas Well	EMERY	NENE	3	18S-7E
43-015-30385-00-00	USA 11-70	Gas Well	EMERY	SWSE	11	18S-7E
43-015-30386-00-00	USA 11-71	Gas Well	EMERY	SWNE	11	18S-7E
43-015-30387-00-00	USA 11-72	Gas Well	EMERY	NWNW	11	18S-7E
43-015-30388-00-00	USA 11-73	Gas Well	EMERY	NWSW	11	18S-7E
43-015-30389-00-00	USA 34-80	Gas Well	EMERY	SENE	34	17S-7E
43-015-30390-00-00	USA 34-82	Gas Well	EMERY	SESW	34	17S-7E
43-015-30393-00-00	ST OF UT EE 06-138	Gas Well	EMERY	NENW	6	17S-9E
43-015-30396-00-00	ST OF UT AA 07-106	Gas Well	EMERY	NWNE	7	17S-8E
43-015-30437-00-00	ST OF UT BB 09-119	Gas Well	EMERY	SESW	9	17S-8E
43-015-30438-00-00	ST OF UT CC 10-124	Gas Well	EMERY	SENE	10	17S-8E
43-015-30439-00-00	ST OF UT DD 31-98	Gas Well	EMERY	NWSW	31	17S-8E
43-015-30440-00-00	FEDERAL T 27-85	Gas Well	EMERY	SENW	27	18S-7E
43-015-30441-00-00	UP&L 06-102	Gas Well	EMERY	NENW	6	17S-8E
43-015-30442-00-00	UP&L 06-104	Gas Well	EMERY	NESE	6	17S-8E
43-015-30443-00-00	WM S IVIE ET AL 09-118	Gas Well	EMERY	SWNE	9	17S-8E

API Well Number	Well Name	Well Type	County Name	Qtr/Qtr	Section	Twn-Rng
43-015-30444-00-00	ST OF UT BB 09-120	Gas Well	EMERY	NESE	9	17S-8E
43-015-30445-00-00	FEDERAL A 26-88	Gas Well	EMERY	SWNW	26	18S-7E
43-015-30446-00-00	FEDERAL A 35-89	Gas Well	EMERY	NWSW	35	18S-7E
43-015-30447-00-00	FEDERAL C 23-84	Gas Well	EMERY	NESW	23	18S-7E
43-015-30448-00-00	FEDERAL P 3-92	Gas Well	EMERY	SESW	3	18S-7E
43-015-30449-00-00	FEDERAL P 3-93	Gas Well	EMERY	SWNW	3	18S-7E
43-015-30450-00-00	FEDERAL T 21-94	Gas Well	EMERY	NENE	21	18S-7E
43-015-30451-00-00	FEDERAL T 22-69	Gas Well	EMERY	NENE	22	18S-7E
43-015-30452-00-00	FEDERAL T 22-83	Gas Well	EMERY	SWSE	22	18S-7E
43-015-30453-00-00	FEDERAL T 22-91	Gas Well	EMERY	NENW	22	18S-7E
43-015-30454-00-00	ST OF UT CC 10-123	Gas Well	EMERY	NWNW	10	17S-8E
43-015-30455-00-00	FEDERAL T 27-86	Gas Well	EMERY	SENE	27	18S-7E
43-015-30456-00-00	FEDERAL T 27-87	Gas Well	EMERY	SESE	27	18S-7E
43-015-30457-00-00	FEDERAL T 27-90	Gas Well	EMERY	NWSW	27	18S-7E
43-015-30458-00-00	ST OF UT FF 10-125	Gas Well	EMERY	NESW	10	17S-8E
43-015-30459-00-00	ST OF UT FF 11-129	Gas Well	EMERY	NWNW	11	17S-8E
43-015-30462-00-00	ST OF UT FF 11-130	Gas Well	EMERY	NWSW	11	17S-8E
43-015-30478-00-00	GARDNER TRUST ET AL 16-121	Gas Well	EMERY	NENE	16	17S-8E
43-015-30479-00-00	ST OF UT BB 05-107	Gas Well	EMERY	SENW	5	17S-8E
43-015-30480-00-00	ST OF UT BB 05-108	Gas Well	EMERY	NWSW	5	17S-8E
43-015-30481-00-00	ST OF UT BB 05-109	Gas Well	EMERY	SENE	5	17S-8E
43-015-30482-00-00	ST OF UT BB 05-110	Gas Well	EMERY	SWSE	5	17S-8E
43-015-30483-00-00	UP&L 06-103	Gas Well	EMERY	NESW	6	17S-8E
43-015-30484-00-00	AMERICA WEST GROUP ET AL 15-126	Gas Well	EMERY	NENW	15	17S-8E
43-015-30485-00-00	W H LEONARD ET AL 15-127	Gas Well	EMERY	NENE	15	17S-8E
43-015-30486-00-00	ROWLEY 08-111	Gas Well	EMERY	SENW	8	17S-8E
43-015-30490-00-00	SWD 4	Water Disposal Well	EMERY	SENE	15	17S-8E
43-015-30495-00-00	SEELEY 08-112	Gas Well	EMERY	NENE	8	17S-8E
43-015-30496-00-00	ST OF UT BB 08-113	Gas Well	EMERY	NWSE	8	17S-8E
43-015-30497-00-00	ST OF UT AA 07-105	Gas Well	EMERY	SWNW	7	17S-8E
43-015-30498-00-00	ST OF UT 01-97	Gas Well	EMERY	SENE	1	18S-7E
43-015-30499-00-00	ST OF UT GG 03-122	Gas Well	EMERY	SWSW	3	17S-8E
43-015-30500-00-00	ST OF UT HH 03-133	Gas Well	EMERY	SWSE	3	17S-8E
43-015-30501-00-00	SEELEY FARMS 09-117	Gas Well	EMERY	NWNW	9	17S-8E
43-015-30502-00-00	ST OF UT GG 15-128	Gas Well	EMERY	NWSW	15	17S-8E
43-015-30503-00-00	ST OF UT BB 04-116	Gas Well	EMERY	SWSE	4	17S-8E
43-015-30504-00-00	ST OF UT GG 04-115	Gas Well	EMERY	NESW	4	17S-8E
43-015-30505-00-00	BURNSIDE 14-132	Gas Well	EMERY	NWNE	14	17S-8E
43-015-30506-00-00	ST OF UT T 36-100	Gas Well	EMERY	NESE	36	16S-7E
43-015-30507-00-00	UT FED KK 01-140	Gas Well	EMERY	SENW	1	17S-7E
43-015-30508-00-00	ST OF UT II 36-96	Gas Well	EMERY	NWSE	36	17S-7E
43-015-30509-00-00	ST OF UT II 36-95	Gas Well	EMERY	NWNE	36	17S-7E
43-015-30510-00-00	SWD 5	Water Disposal Well	EMERY	SESE	23	17S-8E
43-015-30511-00-00	UP&L FED 01-101	Gas Well	EMERY	SENE	1	17S-7E
43-015-30520-00-00	ST OF UT SS 22-165	Gas Well	EMERY	NENE	22	17S-8E
43-015-30521-00-00	ZIONS FED 35-135R (RIG SKID)	Gas Well	EMERY	NESW	35	16S-7E
43-015-30528-00-00	ST OF UT 14-170	Gas Well	EMERY	SWSE	14	17S-8E
43-015-30529-00-00	CONOVER 14-171	Gas Well	EMERY	NWSW	14	17S-8E
43-015-30530-00-00	ST OF UT 36-139	Gas Well	EMERY	NWSW	36	16S-7E
43-015-30533-00-00	ST OF UT FO 02-186	Gas Well	EMERY	NENW	2	17S-8E
43-015-30549-00-00	ST OF UT JJ 03-160	Gas Well	EMERY	NWNW	3	17S-8E
43-015-30550-00-00	ST OF UT 36-138	Gas Well	EMERY	SWNW	36	16S-7E
43-015-30551-00-00	UT FED P 12-153	Gas Well	EMERY	NWNW	12	18S-7E
43-015-30552-00-00	ST OF UT CC 03-161	Gas Well	EMERY	SENE	3	17S-8E
43-015-30553-00-00	ST OF UT FO 02-188	Gas Well	EMERY	NWSW	2	17S-8E
43-015-30554-00-00	ST OF UT BB 04-158	Gas Well	EMERY	NENW	4	17S-8E
43-015-30555-00-00	ST OF UT BB 04-159	Gas Well	EMERY	SWNE	4	17S-8E
43-015-30556-00-00	MALONE 14-131	Gas Well	EMERY	SWNW	14	17S-8E
43-015-30559-00-00	UT FED KK 01-141	Gas Well	EMERY	SESE	1	17S-7E
43-015-30560-00-00	ST OF UT FO 02-189	Gas Well	EMERY	SWNE	2	17S-8E
43-015-30561-00-00	ST OF UT GG 15-184	Gas Well	EMERY	NWSE	15	17S-8E
43-015-30562-00-00	STATE OF UTAH "LL" 31-20	Gas Well	EMERY	NWNW	31	17S-8E
43-015-30566-00-00	ST OF UT "KK" 32-145	Gas Well	EMERY	NESE	32	16S-8E
43-015-30567-00-00	ST OF UT "KK" 32-144	Gas Well	EMERY	SWSW	32	16S-8E
43-015-30568-00-00	ST OF UT "AA" 18-153	Gas Well	EMERY	SESW	18	17S-8E

API Well Number	Well Name	Well Type	County Name	Qtr/Qtr	Section	Twn-Rng
43-015-30569-00-00	ST OF UT "AA" 07-146	Gas Well	EMERY	NESW	7	17S-8E
43-015-30570-00-00	ST OF UT "AA" 18-154	Gas Well	EMERY	NESE	18	17S-8E
43-015-30571-00-00	ST OF UT "AA" 17-156	Gas Well	EMERY	SWSE	17	17S-8E
43-015-30572-00-00	ST OF UT "AA" 18-149	Gas Well	EMERY	SENW	18	17S-8E
43-015-30573-00-00	ST OF UT "MM" 20-192	Gas Well	EMERY	SENW	20	17S-8E
43-015-30574-00-00	ST OF UT "MM" 20-193	Gas Well	EMERY	NENE	20	17S-8E
43-015-30575-00-00	ST OF UT MM 20-194	Gas Well	EMERY	NWSW	20	17S-8E
43-015-30576-00-00	ST OF UT AA 07-147	Gas Well	EMERY	SESE	7	17S-8E
43-015-30577-00-00	ST OF UT BB 08-148	Gas Well	EMERY	NWSW	8	17S-8E
43-015-30578-00-00	ST OF UT AA 18-150	Gas Well	EMERY	NWNE	18	17S-8E
43-015-30579-00-00	ST OF UT NN 19-157	Gas Well	EMERY	NENE	19	17S-8E
43-015-30580-00-00	ST OF UT AA 17-152	Gas Well	EMERY	NENE	17	17S-8E
43-015-30581-00-00	ST OF UT OO 16-190	Gas Well	EMERY	NESW	16	17S-8E
43-015-30582-00-00	ST OF UT PP 16-191	Gas Well	EMERY	NESE	16	17S-8E
43-015-30583-00-00	ST OF UT AA 17-151	Gas Well	EMERY	NENW	17	17S-8E
43-015-30585-00-00	ST OF UT MM 21-195	Gas Well	EMERY	NENW	21	17S-8E
43-015-30586-00-00	ST OF UT GG 21-163	Gas Well	EMERY	NENE	21	17S-8E
43-015-30587-00-00	ZIONS FED 35-137	Gas Well	EMERY	NESE	35	16S-7E
43-015-30589-00-00	UTAH FED 01-205D	Gas Well	EMERY	SENW	1	17S-7E
43-015-30590-00-00	ZIONS FED 02-134	Gas Well	EMERY	NWNW	2	17S-7E
43-015-30591-00-00	UTAH FED 12-197	Gas Well	EMERY	SENE	12	17S-7E
43-015-30592-00-00	ST OF UT QQ 31-201	Gas Well	EMERY	SESW	31	16S-8E
43-015-30593-00-00	ST OF UT AA 17-155	Gas Well	EMERY	SWSW	17	17S-8E
43-015-30601-00-00	UTAH FED 12-199	Gas Well	EMERY	NESE	12	17S-7E
43-015-30602-00-00	UTAH FED 35-196	Gas Well	EMERY	NENW	35	16S-7E
43-015-30603-00-00	UTAH FED 35-136	Gas Well	EMERY	SWNE	35	16S-7E
43-015-30604-00-00	UT FED 12-200D	Gas Well	EMERY	NESE	12	17S-7E
43-015-30605-00-00	UT FED 12-198D	Gas Well	EMERY	SENE	12	17S-7E
43-015-30606-00-00	ST OF UT QQ 31-204D	Gas Well	EMERY	SESW	31	16S-8E
43-015-30607-00-00	ST OF UT QQ 31-203D	Gas Well	EMERY	SESW	31	16S-8E
43-015-30608-00-00	ST OF UT QQ 31-202D	Gas Well	EMERY	SESW	31	16S-8E
43-015-30609-00-00	ST OF UT HH 23-166	Gas Well	EMERY	NENW	23	17S-8E

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Request to Transfer Application or Permit to Drill

(This form should accompany a Sundry Notice, Form 9, requesting APD transfer)

Well name:	Federal T 22-83
API number:	4301530452
Location:	Qtr-Qtr: SWSE Section: 22 Township: 18S Range: 7E
Company that filed original application:	Chevron U.S.A. Inc.
Date original permit was issued:	
Company that permit was issued to:	Chevron U.S.A. Inc.

Check one	Desired Action:
<input type="checkbox"/>	Transfer pending (unapproved) Application for Permit to Drill to new operator
<input type="checkbox"/>	The undersigned as owner with legal rights to drill on the property, hereby verifies that the information as submitted in the pending Application for Permit to Drill, remains valid and does not require revision. The new owner of the application accepts and agrees to the information and procedures as stated in the application.
<input checked="" type="checkbox"/>	Transfer approved Application for Permit to Drill to new operator
<input type="checkbox"/>	The undersigned as owner with legal rights to drill on the property as permitted, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.	Yes	No
If located on private land, has the ownership changed?		<input checked="" type="checkbox"/>
<input type="checkbox"/> If so, has the surface agreement been updated?		
Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location?		<input checked="" type="checkbox"/>
Have there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well?		<input checked="" type="checkbox"/>
Have there been any changes to the access route including ownership or right-of-way, which could affect the proposed location?		<input checked="" type="checkbox"/>
Has the approved source of water for drilling changed?		<input checked="" type="checkbox"/>
Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation?		<input checked="" type="checkbox"/>
Is bonding still in place, which covers this proposed well? Bond No. <u>UT-0848</u>	<input checked="" type="checkbox"/>	

Any desired or necessary changes to either a pending or approved Application for Permit to Drill that is being transferred, should be filed on a Sundry Notice, Form 9, or amended Application for Permit to Drill, Form 3, as appropriate, with necessary supporting information as required.

Name (please print) James L. Death Title Vice President-Land
Signature James L. Death Date 8/16/04
Representing (company name) XTO ENERGY INC.

The person signing this form must have legal authority to represent the company or individual(s) to be listed as the new operator on the Application for Permit to Drill.

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH

2. CDW

3. FILE

X Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective:

8/1/2004

FROM: (Old Operator):N0210-Chevron USA, Inc
11111 S Wilcrest
Houston, TX 77099

Phone: 1-(281) 561-4991

TO: (New Operator):N2615-XTO Energy Inc
2700 Farmington Ave, Bldg K Suite 1
Farmington, NM 87401

Phone: 1-(505) 324-1090

CA No.

Unit:

WELL(S)

NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS	
USA 34-80	34	170S	070E	4301530389	12765	Federal	GW	P	
USA 34-82	34	170S	070E	4301530390	12821	Federal	GW	S	
USA 3-75	03	180S	070E	4301530384	12822	Federal	GW	P	
FEDERAL P 3-92	03	180S	070E	4301530448	13209	Federal	GW	P	
FEDERAL P 3-93	03	180S	070E	4301530449	13210	Federal	GW	S	
USA 11-70	11	180S	070E	4301530385		Federal	GW	APD	C
USA 11-71	11	180S	070E	4301530386		Federal	GW	APD	C
USA 11-72	11	180S	070E	4301530387	12824	Federal	GW	P	
USA 11-73	11	180S	070E	4301530388		Federal	GW	APD	C
FEDERAL T 21-94	21	180S	070E	4301530450		Federal	GW	APD	C
FEDERAL T 22-69	22	180S	070E	4301530451	12818	Federal	GW	P	
FEDERAL T 22-83	22	180S	070E	4301530452		Federal	GW	APD	C
FEDERAL T 22-91	22	180S	070E	4301530453		Federal	GW	APD	C
FEDERAL C 23-84	23	180S	070E	4301530447		Federal	GW	APD	C
FEDERAL A 26-88	26	180S	070E	4301530445		Federal	GW	APD	C
FEDERAL T 27-85	27	180S	070E	4301530440		Federal	GW	APD	C
FEDERAL T 27-86	27	180S	070E	4301530455		Federal	GW	APD	C
FEDERAL T 27-87	27	180S	070E	4301530456	12817	Federal	GW	P	
FEDERAL T 27-90	27	180S	070E	4301530457		Federal	GW	APD	C
FEDERAL A 35-89	35	180S	070E	4301530446	12819	Federal	GW	P	

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 9/28/20042. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 9/28/20043. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 7/19/20044. Is the new operator registered in the State of Utah: YES Business Number: 5655506-01435. If **NO**, the operator was contacted on:6a. (R649-9-2) Waste Management Plan has been received on: to follow6b. Inspections of LA PA state/fee well sites complete on: being worked

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM not yet BIA n/a

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: n/a

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 9/28/2004

DATA ENTRY:

- Changes entered in the Oil and Gas Database on: 9/30/2004
- Changes have been entered on the Monthly Operator Change Spread Sheet on: 9/30/2004
- Bond information entered in RBDMS on: 9/30/2004
- Fee/State wells attached to bond in RBDMS on: 9/30/2004
- Injection Projects to new operator in RBDMS on: 9/30/2004
- Receipt of Acceptance of Drilling Procedures for APD/New on: 9/28/2004

FEDERAL WELL(S) BOND VERIFICATION:

- Federal well(s) covered by Bond Number: 579173

INDIAN WELL(S) BOND VERIFICATION:

- Indian well(s) covered by Bond Number: n/a

FEE & STATE WELL(S) BOND VERIFICATION:

- (R649-3-1) The NEW operator of any fee well(s) listed covered by Bond Number 104312762
- The FORMER operator has requested a release of liability from their bond on: n/a
The Division sent response by letter on: n/a

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The FORMER operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 10/5/2004

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other		5. Lease Serial No. UTU-68538
2. Name of Operator XTO ENERGY INC.		6. If Indian, Allottee or Tribe Name
3a. Address 2700 Farmington Ave. Bldg K, Suite 1 Farmington, NM 87401	3b. Phone No. (include area code) (505) 324-1090	7. If Unit or CA/Agreement, Name and/or No.
4. Location of Well (Footage, Sec., T., R., M., or Survey Description)		8. Well Name and No. All Wells on Lease
		9. API Well No. Multiple
		10. Field and Pool, or Exploratory Area Buzzard's Bench
		11. County or Parish, State Emery, Utah

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other <u>Operator Change</u>
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Effective August 1, 2004, the operator for lease # UTU 68538 changed from Chevron U.S.A. Inc. to XTO ENERGY INC.

XTO ENERGY's Nationwide Bond is ~~579473~~.

UTB000138
(Surety ID: 104312750)

CONFIDENTIAL

RECEIVED
MOAB FIELD OFFICE
2004 SEP 29 P 3:02
DEPT OF THE INTERIOR
BUREAU OF LAND MGMT

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Signature	Edwin S. Ryan JR	Title	SR. VP-Land
Signature	Edwin S. Ryan JR	Date	9/27/04

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by ACCEPTED	Title Division of Resources Moab Field Office	Date SEP 29 2004
Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.		
Office		

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

cc: UDOGM

Conditions Attached

RECEIVED
OCT 27 2004
DIV. OF OIL, GAS & MIN.

API Well Number	Well Name	Well Type	Well Status	County Name	Lease No.	Qtr/Qtr	Section	Location (Twn-Rng)
43-015-30440-00-00	FEDERAL T 27-85 ✓	Gas Well	Approved permit (APD); not yet spudded	EMERY	UTU68538	SENW	27	18S-7E
43-015-30450-00-00	FEDERAL T 21-94 ✓	Gas Well	Approved permit (APD); not yet spudded	EMERY	UTU68538	NENE	21	18S-7E
43-015-30451-00-00	FEDERAL T 22-69 ✓	Gas Well	Producing	EMERY	UTU68538	NENE	22	18S-7E
43-015-30452-00-00	FEDERAL T 22-83 ✓	Gas Well	Approved permit (APD); not yet spudded	EMERY	UTU68538	SWSE	22	18S-7E
43-015-30453-00-00	FEDERAL T 22-91 ✓	Gas Well	Approved permit (APD); not yet spudded	EMERY	UTU68538	NENW	22	18S-7E
43-015-30455-00-00	FEDERAL T 27-86 ✓	Gas Well	Approved permit (APD); not yet spudded	EMERY	UTU68538	SENE	27	18S-7E
43-015-30456-00-00	FEDERAL T 27-87 ✓	Gas Well	Producing	EMERY	UTU68538	SESE	27	18S-7E
43-015-30457-00-00	FEDERAL T 27-90 ✓	Gas Well	Approved permit (APD); not yet spudded	EMERY	UTU68538	NWSW	27	18S-7E

XTO Energy Inc.
Well Nos. T 27-87, T 22-69, T 22-83, T 27-85,
T 27-86, T 27-90, T 22-91 and T 21-94
Sections 21, 22 and 27 , T. 18 S., R. 7 E.
Lease UTU68538
Emery County, Utah

CONDITIONS OF ACCEPTANCE

Acceptance of these applications does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be advised that XTO Energy Inc. is considered to be the operator of the above wells effective August 1, 2004, and is responsible under the terms and conditions of the lease for the operations conducted on the leased lands.

Bond coverage for these well is provided by UTB000138 (Principal – XTO Energy Inc.) via surety consent as provided for in 43 CFR 3104.2.

This office will hold the aforementioned operator and bond liable until the provisions of 43CFR 3106.7-2 continuing responsibility are met.

NOTE:

- Well Nos. T 22-83, T 27-85 and T 27-86 are approved applications that have not yet been drilled. BLM approval to drill at these locations expires 5/23/05.

Well Nos. T 27-90, T 22-91 and T 22-94 are approved applications that have not yet been drilled. BLM approval to drill at these locations expires 6/15/05.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

RECEIVED
DEC 14 2004
DIV. OF OIL, GAS & MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
XTO ENERGY INC.

3. ADDRESS OF OPERATOR:
2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401

PHONE NUMBER:
(505) 324-1090

5. LEASE DESIGNATION AND SERIAL NUMBER:
UTU-68538

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:
Federal T 22-83

9. API NUMBER:
4301530452

10. FIELD AND POOL, OR WILDCAT:
Undesignated

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 539' FSL x 1831' FEL

COUNTY: Emery

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 22 18S 7E S

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. acquired the above listed well in August 2004. A change of operator was submitted on 09/24/04 reflecting this change. It is XTO's intention to drill this well during the 2005 drilling season. XTO hereby requests a one year extension of the existing permit.

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 12-16-04
By: [Signature]

COPY SENT TO OPERATOR

Date: 12-16-04
Initials: [Signature]

NAME (PLEASE PRINT) Kyla Vaughan

TITLE Regulatory Compliance Tech

SIGNATURE

[Signature]

DATE 12/10/2004

(This space for State use only)

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

RECEIVED
DEC 14 2004
DIV. OF OIL, GAS & MINING

API: 4301530452
Well Name: Federal T 22-83
Location: SW SE S22, T18S, R7E
Company Permit Issued to: Texaco Exploration & Production
Date Original Permit Issued: 2/9/2000

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☒

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐

Kyla Vaughan
Signature

12/10/2004
Date

Title: Regulatory Compliance Tech

Representing: XTO Energy, Inc.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-68538
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (505) 324-1090		8. WELL NAME and NUMBER: Federal T 22-83
10. FIELD AND POOL, OR WILDCAT: Undesignated		9. API NUMBER: 4301530452

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 539' FSL x 1831' FEL COUNTY: Emery

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 22 18S 7E S STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 4/13/2005	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Well Name Change
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.


XTO is changing the name of the above listed well to the following:

Federal T 18-7-22-34 effective immediately

RECEIVED

APR 19 2005

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Kyla Vaughan	TITLE Regulatory Compliance Tech
SIGNATURE 	DATE 4/13/2005

(This space for State use only)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>	5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-68535
2. NAME OF OPERATOR: XTO ENERGY INC.	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401	7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 539' FSL & 1831' FEL	8. WELL NAME and NUMBER: FEDERAL T 18-7-22 #34
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SESW 22 18S 07E	9. API NUMBER: 43-015-30452
	10. FIELD AND POOL, OR WILDCAT:

CONFIDENTIAL

COUNTY: EMERY

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input checked="" type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. proposes to change the casing in this new drill from 8-5/8", K-55 casing to 8-5/8", J-55 casing. We also plan to change the 5-1/2", N-80, 17# casing to 5-1/2", J-55, 15.5# casing. The setting depths will remain the same for this drill.

The previous well name was: Federal T 22 #83.

RECEIVED

MAY 12 2005

DIV. OF OIL, GAS & MINING

COPY SENT TO OPERATOR
Date: 5-13-05
Initials: GHD

NAME (PLEASE PRINT) HOLLY C. PERKINS TITLE REGULATORY COMPLIANCE TECH
SIGNATURE *Holly C. Perkins* DATE 5/6/2005

(This space for State use only)

Accepted by the
Utah Division of
Oil, Gas and Mining

Federal Approval Of This
Action Is Necessary

Date: 5/12/05

By: *[Signature]*

See Instructions on Reverse Side

Well name:

Operator:

String type: Surface

Project ID:

Location: Emery County, Utah

Design parameters:

Collapse

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Environment:

H2S considered? No
Surface temperature: 65 °F
Bottom hole temperature: 69 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 300 ft

Burst:

Design factor 1.00

Cement top: Surface

Burst

Max anticipated surface pressure: 0 psi
Internal gradient: 0.436 psi/ft
Calculated BHP 131 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.

Neutral point: 262 ft

Non-directional string.

Re subsequent strings:

Next setting depth: 4,000 ft
Next mud weight: 8.400 ppg
Next setting BHP: 1,745 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 300 ft
Injection pressure 300 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	300	8.625	24.00	J-55	ST&C	300	300	7.972	14.4
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	131	1370	10.469	131	2950	22.54	7	244	33.90 J

Prepared by: Dustin K. Doucet
Utah Div. of Oil & Mining

Phone: (801) 538-5281
FAX: (801)359-3940

Date: May 11,2005
Salt Lake City, Utah

ENGINEERING STIPULATIONS -

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name	
Operator:	
String type: Production	Project ID:
Location: Emery County, Utah	

Design parameters:

Collapse

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:

Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 65 °F
Bottom hole temperature: 121 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,500 ft

Cement top: 3,213 ft

Burst

Max anticipated surface pressure: 0 psi
Internal gradient: 0.436 psi/ft
Calculated BHP 1,745 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Non-directional string.

Tension is based on air weight.
Neutral point: 3,491 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	4000	5.5	15.50	J-55	ST&C	4000	4000	4.825	125.4
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	1745	4040	2.315	1745	4810	2.76	62	202	3.26 J

Prepared by: Dustin K. Doucet
Utah Div. of Oil & Mining

Phone: (801) 538-5281
FAX: (801) 359-3940

Date: May 11, 2005
Salt Lake City, Utah

ENGINEERING STIPULATIONS -

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: XTO Energy Inc.
Address: 2700 Farmington Ave, K #1
city Farmington
state NM zip 87401

Operator Account Number: N 2615

Phone Number: (505) 324-1090

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4301530452	FEDERAL T 18-7-22-34		NWSE	22	18S	07E	EMERY
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
A	99999	14718	4/28/2005			5/19/05	
Comments: <u>FRSD</u>							CONFIDENTIAL

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
Comments:							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Kelly K Small
Name (Please Print)
Kelly K Small
Signature
Drilling Assistant
Title
5/19/05
Date

RECEIVED

MAY 13 2005

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
XTO ENERGY INC.

3. ADDRESS OF OPERATOR:
2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401

PHONE NUMBER:
(505) 324-1090

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 539' FSL x 1,831' FEL

COUNTY: Emery

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 22 18S 07E S

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:
UTU-68538

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
N/A

7. UNIT or CA AGREEMENT NAME:
N/A

8. WELL NAME and NUMBER:
Federal T 18-7-22-34

9. API NUMBER:
4301530452

10. FIELD AND POOL, OR WILDCAT:
Ferron Coal

CONFIDENTIAL

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON	
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Well spud & set conductor csg	
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION		

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. spudded 17-1/2" hole on 04/28/05. Set 13-3/8 conductor csg @ 42'. Cmt'd csg.

NAME (PLEASE PRINT) Kelly K. Small

TITLE Drilling Assistant

SIGNATURE

Kelly K. Small

DATE 5/19/2005

(This space for State use only)

RECEIVED

MAY 26 2005

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-68538
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME: N/A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 539' FSL x 1,831' FEL		8. WELL NAME and NUMBER: Federal T 18-7-22-34
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 22 18S 07E S		9. API NUMBER: 4301530452
COUNTY: Emery		10. FIELD AND POOL, OR WILDCAT: Ferron Coal
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Set & cmt surf csg
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

5/11/05: Drld to 325'. TIH w/8-5/8", 24#, J-55, ST&C csg to 321.92'. Cmt'd surf csg w/220 sx CI "G" cmt w/2% CaCl2 & 1/4 PPS Flocele.

NAME (PLEASE PRINT) Kelly K. Small	TITLE Drilling Assistant
SIGNATURE <i>Kelly K. Small</i>	DATE 5/19/2005

(This space for State use only)

RECEIVED
MAY 26 2005

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL

OIL WELL ☐

GAS WELL ☒

OTHER ☐

CONFIDENTIAL

2. NAME OF OPERATOR:

XTO ENERGY INC.

3. ADDRESS OF OPERATOR:

2700 Farmington Ave. Bldg K CITY Farmington

STATE NM ZIP 87401

PHONE NUMBER:

(505) 324-1090

5. LEASE DESIGNATION AND SERIAL NUMBER:

UTU-68538

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

FEDERAL T 18-7-22-34

9. API NUMBER:

4301530452

10. FIELD AND POOL, OR WILDCAT:

FERRON SAND

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 539' FSL x 1,831' FEL

COUNTY: EMERY

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 22 18S 07E S

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: MAY 2005 DRLG ACTIVITY
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

See attached for May 2005 drilling activity.

NAME (PLEASE PRINT) Kelly K. Small

TITLE Drilling Assistant

SIGNATURE

Kelly K. Small

DATE 6/2/2005

(This space for State use only)

RECEIVED
JUN 06 2005
DIV. OF OIL, GAS & MINING

Farmington Monthly Report

CONFIDENTIAL

FEDERAL T

Well # 18-7-22-34

FERRON

Objective: Drill & Complete**Rig:** Leon Ross Drlg**AFE:** 504578**1st Rept:** 10/14/1999

5/6/05 Notified Don Stevens, BLM, Price, Utah on 4/28/05 of spud & conductor csg. Spudded 17-1/2" hole & set 13-3/8" conductor csg @ 42'. Cmt'd csg. Built cellar. Rpts suspended pending further activity.

DWC: \$8,600**CWC:** \$29,100**DMC:** \$0**CMC:** \$0

===== FEDERAL T #18-7-22-34 =====

Rig: Leon Ross Drlg

5/12/05 RD Leon Ross drlg & cmtg crew @ 325' (283'/24 hrs). Surv: 0 deg @ 325'. Bit #1, 12-1/4" (no bit info), in @ 42', out @ 325' (283'/1-1/2 hrs). RU/RD 3 hrs, drlg 1-1/2 hrs, surv 1/4 hr, trip 1 hr, C&C 1 hr, rn csg/cmt 4-1/4 hrs (11 ttl hrs). PU & TIH w/8 jts 8-5/8", 24#, J-55, ST&C csg to 321.92', IFV @ 281.50'. MIRU Big 4 cmtg. Cmt'd csg w/220 sx C1 "G" regular cmt w/2% CaCl2 & 1/4 PPS Flocele (mixed @ 15.8 ppg, 1.15 cuft/sx). Disp w/18 BFW. Bmpd plg w/500 psig (200 psig over late pmp press). Float held OK. Circ good cmt rtns to surf. RDMO Big 4 cmtg & Leon Ross drlg.

DWC: \$22,180**CWC:** \$51,280**DMC:** \$0**CMC:** \$0**Casing Location:** Surface**DV Depth:** 0.00**Marker 1 Depth:** 0.00**FC Depth:** 281.50**Marker 2 Depth:** 0.00

Qty	Type	Description	Cond	Top Btm		Length
				Depth	Depth	
1	manual	8-5/8" Texas Pattern Guide Shod	New	321.27	321.92	0.65'
1	Casing	8-5/8", 24.0#, J-55, ST&C Shoe Jt	New	281.50	321.27	39.77'
1	manual	8-5/8" IFV	New	281.50	281.50	0.00'
7	Casing	8-5/8", 24.0#, J-55, ST&C Casing	New	3.60	281.50	277.90'
Total						318.32'
- Cut Off						-3.60'
Landed @						321.92'

===== FEDERAL T #18-7-22-34 =====

RECEIVED

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

JUN 13 2005

FORM 9

DIV. OF OIL, GAS & MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-68538
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 539' FSL x 1,831' FEL		8. WELL NAME and NUMBER: FEDERAL T 18-7-22-34
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 22 18S 07E S		9. API NUMBER: 4301530452
COUNTY: EMERY		10. FIELD AND POOL, OR WILDCAT: FERRON COAL
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: TD & SET PROD
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	CSG

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

6/01/05: PT BOPE & surf csg to 1,000 psig f/30 min. Held OK.
6/02/05: DO cmt & FE fr/240' to 325'.
6/03/05: Drld to 1,689'.
6/04/05: Drld to 2,090'.
6/05/05: Drld to 3,314'.
6/06/05: Reached driller's TD of 3,496'. Circ f/logs & csg. RU loggers & logged op hole. Std TIH w/5-1/2" prod csg.
6/07/05: Fin TIH w/5-1/2", 15.5#, J-55, ST&C csg to 3,458.66'. Cmt prod csg w/240 sx Premium V (five) cmt w/16% gel, 10 PPS Gilsonite, 3 PPS GR-3, & 3% salt followed by 175 sx Premium "G" cmt w/10% Gypsum & 1/4 PPS Flocele. Circ 80 bbls cmt to surf. Released rig @ 12:00 a.m., 06/08/05.

NAME (PLEASE PRINT) Kelly K. Small	TITLE Drilling Assistant
SIGNATURE <i>Kelly K. Small</i>	DATE 6/9/2005

(This space for State use only)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <u>CONFIDENTIAL</u>		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-68538
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 539' FSL x 1,831' FEL		8. WELL NAME and NUMBER: FEDERAL T 18-7-22-34
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 22 18S 07E S		9. API NUMBER: 4301530452
COUNTY: EMERY		10. FIELD AND POOL, OR WILDCAT: FERRON COAL
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input checked="" type="checkbox"/> TEMPORARILY ABANDON	
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: <u>June Monthly Report</u>	
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION		

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

See attached for June 2005 drilling activity.

NAME (PLEASE PRINT) <u>Kelly K. Small</u>	TITLE <u>Regulatory Compliance Tech</u>
SIGNATURE <u>Kelly K. Small</u>	DATE <u>7/6/2005</u>

(This space for State use only)

RECEIVED
JUL 12 2005
DIV. OF OIL, GAS & MINING

Farmington Monthly Report

CONFIDENTIAL

FEDERAL T	Well # 18-07- 22-34	FERRON	Emery, UT
-----------	------------------------	--------	-----------

Objective: Drill & Complete

Rig: Stewart Bros #51

AFE: 504578

1st Rept: 10/14/1999

6/2/05 Tst BOPE @ 325' (283'/24 hrs). RU 6 hrs, tst BOPE 4 hrs (10 ttl hrs). MIRU Stewart Bros. rig #51. Tstd BOPE to 1,000 psig f/30 min. Held OK.

DWC: \$3,250 CWC: \$54,530 DMC: \$0 CMC: \$0

Rig: Stewart Bros #51

6/3/05 Drlg @ 628' (303'/24 hrs). Air. Bit #2, 7-7/8" HTC, XL30A, SN 5073586, 16/16/16, in @ 325' (303'/14-3/4 hrs), WOB 24K, RPM 72, air press 200 psig. RU 4 hrs, drlg 14-3/4 hrs, trip 4-1/2 hrs, repr 3/4 hr. RU non rotating flowline. TIH to 240'. Tgd cmt. Drlg ahead.

DWC: \$11,750 CWC: \$66,280 DMC: \$0 CMC: \$0

Rig: Stewart Bros #51

6/4/05 Drlg @ 1,689' (1,061'/24 hrs). Surv: 1 deg @ 800' & 1-1/2 deg @ 1,300'. Air. Bit #2, 7-7/8" HTC, XL30A, SN 5073586, 16/16/16, in @ 325' (1,364'/37 hrs), WOB 24K, RPM 72, air press 200 psig. Drlg 22-1/4 hrs, surv 1/2 hr, rig serv 1-1/4 hrs. Drlg ahead.

DWC: \$14,280 CWC: \$80,560 DMC: \$0 CMC: \$0

Rig: Stewart Bros #51

6/5/05 Drlg @ 2,090' (401'/24 hrs). Surv: 1-1/4 deg @ 1,800'. Air. Bit #2, 7-7/8" HTC, XL30A, SN 5073586, 16/16/16, in @ 325', out @ 1,810' (1,485'/38-1/2 hrs), WOB 24K, RPM 72, air press 200 psig. Air. Bit #3, 7-7/8" HTC, XL30A, SN 5071806, 16/16/16, in @ 1,810' (280'/4-1/2 hrs), WOB 25K, RPM 72, air press 200 psig. Drlg 6 hrs, surv 1/2 hr, trip 8-3/4 hrs, rig serv 8-1/4 hrs, C&C 1/2 hr. Drld to 1,810'. Circ. TOH w/bit #2. TIH w/bit #3. Drlg ahead.

DWC: \$14,750 CWC: \$95,310 DMC: \$0 CMC: \$0

Rig: Stewart Bros #51

6/6/05 Drlg @ 3,314' (1,224'/24 hrs). Surv: 3/4 deg @ 2,300' & 3/4 deg @ 2,800'. Air. Bit #3, 7-7/8" HTC, XL30A, SN 5071806, 16/16/16, in @ 1,810' (1,504'/27-1/2 hrs), WOB 25K, RPM 72, air press 200 psig. Drlg 23 hrs, surv 1 hr. Drlg ahead.

DWC: \$11,750 CWC: \$107,060 DMC: \$0 CMC: \$0

Rig: Stewart Bros #51

FEDERAL T #18-07-22-34	<=continued=>	FERRON	Emery, UT
------------------------	---------------	--------	-----------

6/7/05 TIH w/5-1/2" prod csg @ 3,496' (driller's TD) (182'/24 hrs). Surv: 1 deg @ 3,496'. Air. Bit #3, 7-7/8" HTC, XL30A, SN 5071806, 16/16/16, in @ 1,810', out @ 3,496' (1,686'/31 hrs), WOB 25K, RPM 72, air press 200 psig. Drlg 3-1/2 hrs, surv 1/2 hr, trip 7-1/2 hrs, C&C 2-1/2 hrs, rn csg 3 hrs, log 7 hrs. Reached driller's TD of 3,496' @ 9:30 a.m., 6/06/05. Circ hole cl. TOH. Filled hole w/130 BPW. TOH. MIRU Schlumberger WL. RIH w/Platform Express logs. Std TIH w/5-1/2" prod csg.

DWC: \$23,609 CWC: \$130,669 DMC: \$0 CMC: \$0

Rig: Stewart Bros #51

6/8/05 Released rig @ 3,496' (driller's TD) (0'/24 hrs). RD 10 hrs, cmt 8 hrs (18 ttl hrs). TIH w/111 jts 5-1/2" 15.5#, J-55, ST&C csg to 3,458.66'. FC @ 3,426.07'. MIRU Big 4 Cmtg. Cmtd prod csg w/240 sx Premium Type V (five) cmt w/16% gel, 10 PPS Gilsonite, 3 PPS GR-3, & 3% salt (mixed @ 11.0 ppg and 3.82 cuft/sx) followed by 175 sx Premium "G" cmt w/10% Gypsum & 1/4 PPS Flocele (mixed @ 14.2 ppg and 1.60 cuft/sx). Disp w/50 BFW. Bumped plug w/1,600 psig (600 psig over late pmp press). Float held OK. Circ 80 bbls cmt to surf. RDMO Big 4 Cmtg. ND BOPE. Set slips & cut csg. Released Stewart Bros. rig #51 @ 12:00 a.m., 06/08/05.

DWC: \$62,171 CWC: \$192,840 DMC: \$0 CMC: \$0

Casing Location: Production

DV Depth: 0.00 Marker 1 Depth: 2,624.36
FC Depth: 3,426.07 Marker 2 Depth: 0.00

Qty	Type	Description	Cond	Top Depth	Btm Depth	Length
1	Other	5-1/2" Float Shoe, non-auto-fill	New	3,457.71	3,458.66	0.95'
1	Casing	5-1/2", 15.5#, J-55, ST&C Shoe Jt	New	3,426.67	3,457.71	31.04'
1	Other	5-1/2" Float Collar, non-auto fill	New	3,426.07	3,426.67	0.60'
25	Casing	5-1/2", 15.5#, J-55, ST&C Casing	New	2,646.29	3,426.07	779.78'
1	Casing	5-1/2", 15.5#, J-55, ST&C Marker Jt	New	2,624.36	2,646.29	21.93'
84	Casing	5-1/2", 15.5#, J-55, ST&C Casing	New	0.00	2,624.36	2,624.36'
Total						3,458.66'
Landed @						3,458.66'

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER ☐

2. NAME OF OPERATOR:
XTO ENERGY INC.

3. ADDRESS OF OPERATOR:
2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401

PHONE NUMBER:
(505) 324-1090

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 539' FSL & 1,831' FEL

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 22 T18S R7E S

COUNTY: EMERY

STATE: UTAH

5. LEASE DESIGNATION AND SERIAL NUMBER:
UTU-68538

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
N/A

7. UNIT or CA AGREEMENT NAME:
N/A

8. WELL NAME and NUMBER:
FEDERAL T 18-7-22-34

9. API NUMBER:
4301530452

10. FIELD AND POOL, OR WILDCAT:
FERRON COAL

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>July Monthly Drlg Rpt</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

See attached for July, 2005 drilling activity.

NAME (PLEASE PRINT) Kelly K. Small

TITLE Regulatory Compliance Tech

SIGNATURE

DATE 8/4/2005

(This space for State use only)

RECEIVED

AUG 08 2005

DIV. OF OIL, GAS & MINING

Farmington Monthly Report

CONFIDENTIAL

FEDERAL T	Well # 18-07-22-34	FERRON
-----------	--------------------	--------

Objective: Drill & Complete**Rig:** Halliburton**AFE:** 504578**1st Rept:** 10/14/1999

7/12/05 7/5/05 to 7/11/05. Backfill reserve pit. MI 15 - 500 bbl frac tks. Inst 5K 5-1/2" frac vlv. MIRU Computalog. Run CBL fr/3,418' to surf. TOC @ surf. RDMO Computalog. MIRU Big Red Hot Oil. Tstd csg to 4,000 psig for 30". Tstd OK. RDMO Big Red Hot Oil. Filled frac tnks w/7,500 BFW (temp 72 deg to 75 deg). Lded annulus w/corrosion inhibitor, biocide & 50 BPW. 7/12/05 MIRU Computalog. TIH w/4" HSC csg gun. Perf L/Ferron Coal w/3 JSPF fr/3,127' - 3,132' (15 holes) & fr/3,144' - 3,159' (45 holes) (23 gm, .46" dia, 120 deg phasing). All depths correlated w/Schlumberger CNL/GR log ran on 6/6/05. RIH w/dmp blr & spot 10 gal 28% HCl @ 3,150'. RDMO Computalog. MIRU Halliburton frac equip. BD lower Ferron coal perfs @ 1,066 psig & 5.0 BPM. A. perfs fr/3,127' - 3,159' w/500 gal 15% HCl. Ppd 8,270 gal 20# linear gel wtr for step rate tst. ATP 1,110 psig @ 40 BPM. SD. ISIP 380 psig. Frac perfs fr/3,127 - 3,159 dwn 5-1/2 csg w/146,100 gal 20# XL gel (delta 140), carrying 4,500# 40/70 sd, 198,500# 20/40 Brady sd & 83,000# 16/30 Brady Sd (treated w/sand wedge and sand wedge NT). Flushed w/3,100 gals 20# lineral gel. Max sd conc 5.0 ppg. ATP 1,531 psig. ISIP 1,150 psig. 5" SIP 1,055 psig. 10" SIP 938 psig. 15" SIP 858 psig. RDMO Halliburton frac equip. Refill 6 - 500 bbl frac tanks w/FW. SWI 2 hr. SIP 0 psig. 3,687 BLWTR.

DWC: \$284,500 **CWC:** \$477,340 **DMC:** \$0 **CMC:** \$0

FEDERAL T #18-07-22-34

Rig: Computalog WL

7/13/05 7/5/05 to 7/11/05. Backfill reserve pit. MI 15 - 500 bbl frac tks. Inst 5K 5-1/2" frac vlv. MIRU Computalog. Run CBL fr/3,418' to surf. TOC @ surf. RDMO Computalog. MIRU Big Red Hot Oil. Tstd csg to 4,000 psig for 30". Tstd OK. RDMO Big Red Hot Oil. Filled frac tnks w/7,500 BFW (temp 72 deg to 75 deg). Lded annulus w/corrosion inhibitor, biocide & 50 BPW. 7/12/05 MIRU Computalog. TIH w/4" HSC csg gun. Perf L/Ferron Coal w/3 JSPF fr/3,127' - 3,132' (15 holes) & fr/3,144' - 3,159' (45 holes) (23 gm, .46" dia, 120 deg phasing). All depths correlated w/Schlumberger CNL/GR log ran on 6/6/05. RIH w/dmp blr & spot 10 gal 28% HCl @ 3,150'. RDMO Computalog. MIRU Halliburton frac equip. BD lower Ferron coal perfs @ 1,066 psig & 5.0 BPM. A. perfs fr/3,127' - 3,159' w/500 gal 15% HCl. Ppd 8,270 gal 20# linear gel wtr for step rate tst. ATP 1,110 psig @ 40 BPM. SD. ISIP 380 psig. Frac perfs fr/3,127 - 3,159 dwn 5-1/2 csg w/146,100 gal 20# XL gel (delta 140), carrying 4,500# 40/70 sd, 198,500# 20/40 Brady sd & 83,000# 16/30 Brady Sd (treated w/sand wedge and sand wedge NT). Flushed w/3,100 gals 20# lineral gel. Max sd conc 5.0 ppg. ATP 1,531 psig. ISIP 1,150 psig. 5" SIP 1,055 psig. 10" SIP 938 psig. 15" SIP 858 psig. RDMO Halliburton frac equip. Refill 6 - 500 bbl frac tanks w/FW. SWI 2 hr. SIP 0 psig. 3,687 BLWTR. Sli blow on csg. MIRU Computalog. RIH w/5-1/2" composite BP & set @ 3,121'. TOH w/WL. MIRU Big Red Hot Oil. Tstd csg to 1,500 psig for 5" w/30 BFW. Tstd OK. RDMO Big Red Hot Oil. Filled 11 frac tks w/5,500 BFW (temp 72 deg to 75 deg & trtd w/biocide). RIH w/dmp blr & spot 5 gal 28% HCl @ 3,086'. TOH & LD dmp blr. TIH w/4" HSC csg gun. Perf U/Ferron Coal w/3 JSPF fr/3,086' - 3,104' (54 holes) (23 gm, .46" dia, 120 deg phasing). All depths correlate w/Schlumberger CNL/GR log ran on 6/6/05. FL @ 40' FS after perf. LD csg gun. RDMO Computalog. 3,717 BLWTR.

RECEIVED

AUG 08 2005

8/4/2005

DWC: \$10,500**CWC: \$487,840****DMC: \$0****CMC: \$0**

FEDERAL T #18-07-22-34

Rig: Computalog WL

7/14/05 MIRU Halliburton frac equip. BD Upper Ferron coal perfs @ 910 psig & 5.0 BPM. A. perfs fr/3,086' - 3,104' w/750 gal 15% HCl @ 10 BPM & 1,180 psig. Ppd 3,100 gal 20# linear gel wtr for step rate tst. ATP 1,680 psig @ 41 BPM. SD. ISIP 1,040 psig. Frac perfs fr/3,086' - 3,104' dwn 5-1/2 csg w/6,400 gals 20# linear gel, 153,060 gal 20# XL gel (delta 140), carrying 4,500# 40/70 sd, 199,500# 20/40 Brady sd & 87,000# 16/30 Brady Sd (treated w/sand wedge and sand wedge NT). Flushed w/3,080 gals 20# linear gel. Max sd conc 5.0 ppg. ATP 2,495 psig. MTP 3,417 psig. ISIP 1,853 psig. 10" SIP 1,560 psig. 15" SIP 1,475 psig. RDMO Halliburton frac equip. 3 hr SIP 250 psig. MIRU Computalog. RIH w/5-1/2" CBP & set @ 3,060'. TOH w/WL. MIRU Big Red Hot Oil. Tstd csg to 2,000 psig for 5". Tstd OK. RDMO Big Red Hot Oil. TIH w/4" HSC csg gun. Perf Ferron Sand w/3 JSPF fr/3,032' - 3,040' (24 holes) (23 gm, .46" dia, 120 deg phasing). All depths correlate w/Schlumberger CNL/GR log ran on 6/6/05. FL @ 40' FS after perf. LD csg gun. RDMO Computalog. 3,717 BLWTR.

DWC: \$235,000**CWC: \$722,840****DMC: \$0****CMC: \$0**

FEDERAL T #18-07-22-34

Rig: Halliburton

7/15/05 MIRU Halliburton frac equip. BD Ferron Sand perfs w/1,000 gal linear gel @ 3,890 psig & 5.0 BPM. A. perfs fr/3,032' - 3,040' w/600 gal 15% HCl @ 10 BPM & 2,170 psig. Frac perfs fr/3,032' - 3,040' dwn 5-1/2 csg w/5,185 gal 20# XL gel (delta 140), 33,917 20# XL carrying 85,300# 20/40 Brady sd (treated w/Expedite). Flushed w/2,900 gals 20# linear gel. Max sd conc 5.0 ppg. ATP 2,273 psig. ISIP 2,038 psig. 45" SIP 1,477 psig. RDMO Halliburton frac equip. 8,693 BLWTR.

DWC: \$90,000**CWC: \$812,840****DMC: \$0****CMC: \$0**

FEDERAL T #18-07-22-34

Rig: Key Energy #906

7/23/05 SICIP 0 psig. MIRU Key Energy Rig #906. ND frac vlv. NU BOP. WO tbq. SDFN. 8,693 BLWTR.

DWC: \$7,300**CWC: \$820,140****DMC: \$0****CMC: \$0**

FEDERAL T #18-07-22-34

Rig: Key Energy #906

7/24/05 SDF Saturday. 8,693 BLWTR.

DWC: \$0**CWC: \$820,140****DMC: \$0****CMC: \$0**

FEDERAL T #18-07-22-34

Rig: Key Energy #906

7/25/05 SDF Sunday. 8,693 BLWTR.

DWC: \$0**CWC: \$820,140****DMC: \$0****CMC: \$0**

FEDERAL T #18-07-22-34

Rig: Key Energy #906

7/26/05 SICIP 0 psig. PU & TIH 109 jts 2-7/8", 6.5#, J-55, EUE, 8rd tbq. Tgd @ 2,866'. Ferron Perfs fr/3,032' - 3,040'. CO fr/2,866' - 3,060' (174' fill). DO CBP @ 3,060'. Tgd @ 3,080'. Perfs fr/3,086' - 3,104'. CO fr/3,080' - 3,121' (41' fill). DO CBP @ 3,121'. Tgd @ 3,345'. Perfs fr/3,127' - 3,132' & 3,144' - 3,159'. CO fr/3,345' - 3,422' (PBTD) (77' fill). Rec marble sized chunks of sticky sd. Circ for 2 hrs. TOH 5 jts tbq. Bit @ 3,270'. SWI. SDFN. Used 220 BFW

for CO. 8,913 BLWTR.

DWC: \$7,500**CWC:** \$827,640**DMC:** \$0**CMC:** \$0

FEDERAL T #18-07-22-34

Rig: Key Energy #906

7/27/05 SITP 0 psig. SICP 80 psig. Bit @ 3,270'. Perfs fr/3,032' - 3,159'. RU swb tls. BFL @ 600' FS. S. 0 BO, 300 BLW, 38 runs, 9 hrs, FFL 2,000' FS. SICP 0 psig. No solids w/fld smpls. Csg flowing during swb runs. RD swb tls. SWI. SDFN. 8,613 BLWTR.

DWC: \$6,700**CWC:** \$834,340**DMC:** \$0**CMC:** \$0

FEDERAL T #18-07-22-34

Rig: Key Energy #906

Forest Gas: 0 MCFPD

Prev Gas: 0 MCFPD

7/28/05 SITP 0 psig, SICP 550 psig. Bit @ 3,270'. Perfs fr/3,032' - 3,159'. RU swb tls. BFL @ 1,500' FS. S. 0 BO, 165 BLW, 20 runs, 8 hrs, FFL 1,500' FS. FCP 380 psig. No solids w/fld smpls. Flwg btw swb runs. RD swb tls. SWI. SDFN. 8,448 BLWTR.

DWC: \$6,200**CWC:** \$840,540**DMC:** \$0**CMC:** \$0

FEDERAL T #18-07-22-34

Rig: Key Energy #906

Forest Gas: 0 MCFPD

Prev Gas: 0 MCFPD

7/29/05 SITP 0 psig, SICP 500 psig. PU & TIH 5 jts tbg. Tgd @ 3,422' (PBTD). LD 6 jts tbg. TOH 103 jts tbg, bit sub & bit. LD bit sub & bit. PU & TIH OPMA, 1 jt 2-7/8" tbg, 2703 Cavin desander, 2-7/8" x 4' tbg sub, 2-7/8" SN & 103 jts 2-7/8" tbg. ND BOP. NU WH. Ld tbg as follows: SN @ 3,240'. EOT @ 3,313'. Ferron Coal perfs fr/3,032' - 3,159'. PBTD @ 3,422'. RIH w/XTO 2.347" tbg broach to SN. LD tbg broach. PU & loaded 2-1/2" x 1-3/4" x 16' RHBC (DV) pmp (XTO #064) w/1" x 1' stnr nip. TIH pmp, 3 - 7/8" x 4' stabilizers, 12 - 7/8" Norris Grade "D" rods w/5 molded guides per rod new fr/XTO stk, 116 - 3/4" Norris Grade "D" rods w/5 molded guides per rod new fr/XTO stk, 3/4" x 2' rod sub & 1-1/4" x 22' PR w/14' lnr. Seated pmp. PT tbg to 500 psig w/3 BFW. Tstd OK. Rlsd press. LS pmp w/rig to 500 psig. GPA. Rlsd press. SWI. RDMO Key Energy #906. 8,451 BLWTR.

DWC: \$30,500**CWC:** \$871,040**DMC:** \$0**CMC:** \$0**Tubing Location:** Lower**ZONE 1 Desc:** Ferron**Top Perf:** 3,127.00**Btm Perf:** 3,040.00 **OH:** No

<u>Qty</u>	<u>Type</u>	<u>Description</u>	<u>Cond</u>	<u>Top Depth</u>	<u>Btm Depth</u>	<u>Length</u>
103	Tubing	2-7/8", 6.5#, J-55, EUE, 8rd Tubing	New	6.00	3,239.08	3,233.08'
1	Tubing	2-7/8" SN	New	3,239.08	3,240.18	1.10'
1	Tubing	2-7/8", 6.5#, J-55, EUE, 8rd Tubing Sub	New	3,240.18	32,444.00	4.22'
1	manual	Tubing - 2-7/8" Cavins 2703 Desander	New	32,444.00	3,264.58	20.18'
1	Tubing	2-7/8", 6.5#, J-55, EUE, 8rd Tubing	New	3,264.58	3,295.96	31.38'
1	Tubing	2-7/8", 6.5#, J-55, EUE, 8rd OPMA Jt	New	3,295.96	3,312.91	16.95'
Total						3,306.91'

Landed @ 3,306.91'

FEDERAL T #18-07-22-34

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL:		OIL WELL <input type="checkbox"/>	GAS WELL <input checked="" type="checkbox"/>	DRY <input type="checkbox"/>	OTHER <input type="checkbox"/>		
b. TYPE OF WORK:		NEW WELL <input checked="" type="checkbox"/>	HORIZ. LATS. <input type="checkbox"/>	DEEP-EN <input type="checkbox"/>	RE-ENTRY <input type="checkbox"/>	DIFF. RESVR. <input type="checkbox"/>	OTHER <input type="checkbox"/>
2. NAME OF OPERATOR: XTO ENERGY INC.						5. LEASE DESIGNATION AND SERIAL NUMBER: UTU68535	
3. ADDRESS OF OPERATOR: 2700 FARMINGTON, K-1 CITY FARMINGTON STATE NM ZIP 87401						6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 539' FSL & 1831' FEL AT TOP PRODUCING INTERVAL REPORTED BELOW: AT TOTAL DEPTH:						7. UNIT or CA AGREEMENT NAME	
10. FIELD AND POOL, OR WILDCAT BUZZARD BENCH						8. WELL NAME and NUMBER: FEDERAL T 18-7-22-34	
11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE 22 18S 7E						9. API NUMBER: 4301560452	
12. COUNTY EMERY						13. STATE UTAH	

14. DATE SPUDDED: 5/6/2005	15. DATE T.D. REACHED: 6/6/2005	16. DATE COMPLETED: 8/6/2005	ABANDONED <input type="checkbox"/>	READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL):
18. TOTAL DEPTH: MD 3,496 TVD	19. PLUG BACK T.D.: MD 3,422 TVD	20. IF MULTIPLE COMPLETIONS, HOW MANY? *			21. DEPTH BRIDGE MD PLUG SET: TVD

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) GEL CV/CAH CN/TDD/HRI, CN/TDD/GR AI/LC/GR	23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)
---	---

24. CASING AND LINER RECORD (Report all strings set in well)									
HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
12-1/4	8-5/8 J55	24		322		220		0	0
7-7/8	5-1/2 J55	15.5		3,459		415		0	0

25. TUBING RECORD									
SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	
2-7/8	3.307								

26. PRODUCING INTERVALS					27. PERFORATION RECORD				
FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS	
(A) FERRON COAL	3,032	3,159			3,127 3,159	0.46	198	Open <input checked="" type="checkbox"/>	Squeezed <input type="checkbox"/>
(B)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.	
DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
	A. w/1750 gals 15% HCl acid. Frac'd w/298,600# 20# XL gel (Delta 140), carrying 13,500# 40/70 sa 596,500# 40/70 sd & 253,000# 16/30 Brady sand.

29. ENCLOSED ATTACHMENTS: <input checked="" type="checkbox"/> ELECTRICAL/MECHANICAL LOGS <input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION	<input type="checkbox"/> GEOLOGIC REPORT <input type="checkbox"/> CORE ANALYSIS	<input type="checkbox"/> DST REPORT <input type="checkbox"/> OTHER: _____	30. WELL STATUS:
--	--	--	------------------

RECEIVED

AUG 18 2005

DIV. OF OIL, GAS & MINING

31. INITIAL PRODUCTION
INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 8/6/2005	TEST DATE: 8/6/2005	HOURS TESTED: 24	TEST PRODUCTION RATES: →	OIL – BBL: 0	GAS – MCF: 52	WATER – BBL: 0	PROD. METHOD: P
CHOKE SIZE:	TBG. PRESS. 24	CSG. PRESS. 20	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:	TEST DATE:	HOURS TESTED:	TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)
33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
				MANCOS MARKER	2.934
				UPPER FERRON SS	3.026
				TOP OF COAL	3.082
				LOWER FERRON SS	3.160
				TUNUNK	3.444

35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) **HOLLY C. PERKINS**

TITLE **REGULATORY COMPLIANCE TECH**

SIGNATURE *Holly C. Perkins*

DATE **8/10/2005**

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation

- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

4301530452 FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
XTO ENERGY INC.

3. ADDRESS OF OPERATOR:
2700 Farmington, Bldg K-1 Farmington NM 87401

PHONE NUMBER:
(505) 324-1090

5. LEASE DESIGNATION AND SERIAL NUMBER.
UTU-73965

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME

8. WELL NAME and NUMBER
LM LEMMON #10-01

9. API NUMBER

Various (see attached)

10. FIELD AND POOL, OR WILDCAT:
FERRON SANDSTONE

4. LOCATION OF WELL

FOOTAGES AT SURFACE: 660' FSK & 792' FEL

COUNTY: EMERY

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN SESE 10 17S 08E

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start 1/1/2004	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input checked="" type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. acquired wells from Chevron/Texaco on August 1, 2004. Chevron/Texaco failed to file a Notice of Intent to surface commingle these wells and XTO Energy Inc. was unaware until recently that nothing had been filed. We are including with this application for surface commingle a list of the wells in Emery County and a spreadsheet showing production figures for these wells. Each well has its own meter then runs through a central delivery point where allocations are made.

XTO Energy Inc. is requesting approval for the commingle of these wells as well as off-lease measurement. As wells are drilled, additional sundries will be submitted to add to our surface commingle.

COPY SENT TO OPERATOR
Date: 6-15-07
Initials: RM

NAME (PLEASE PRINT) HOLLY C. PERKINS

TITLE REGULATORY COMPLIANCE TECH

SIGNATURE

DATE 5/15/2007

This space for State use only)

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING
DATE: 6/11/07
BY: [Signature]

Federal Approval Of This
Action Is Necessary

RECEIVED
MAY 18 2007

DIV. OF OIL, GAS & MINING

Utah Wells Surface Commingled at Huntington CDP

Well Name	API #	Status	Lease
American West Group 15-128	43-015-30484	Shut In	State
Conover 14-171	43-015-30529	Producing	State
Gardner Trust 16-121	43-015-30478	Producing	State
Lemmon LM 10-01	43-015-30242	Producing	Federal
Malone 14-131	43-015-30556	Producing	State
Rowley 08-111	43-015-30486	Producing	State
Seeley 08-112	43-015-30495	Producing	State
Seeley Farms 09-117	43-015-30501	Producing	State
State of Utah 16-8-31-12D	43-015-30608	Producing	State
State of Utah 16-8-31-32DX	43-015-30634	Producing	State
State of Utah 16-8-31-44D	43-015-30606	Producing	State
State of Utah 16-8-32-43	43-015-30566	Producing	State
State of Utah 17-8-15-14	43-015-30622	Producing	State
State of Utah 17-8-15-33	43-015-30561	Producing	State
State of Utah 17-8-17-32	43-015-30672	Producing	State
State of Utah 17-8-18-12	43-015-30626	Producing	State
State of Utah 17-8-18-24	43-015-30678	Producing	State
State of Utah 17-8-18-31	43-015-30671	Producing	State
State of Utah 17-8-18-43	43-015-30670	Producing	State
State of Utah 17-8-20-22	43-015-30623	Producing	State
State of Utah 17-8-21-33	43-015-30679	Producing	State
State of Utah 17-8-21-41	43-015-30631	Producing	State
State of Utah 17-8-22-14	43-015-30676	Producing	State
State of Utah 17-8-22-21	43-015-30624	Producing	State
State of Utah 17-8-28-12X	43-015-30699	Producing	State
State of Utah 17-8-3-11X	43-015-30635	Producing	State
State of Utah 17-8-4-21	43-015-30620	Producing	State
State of Utah 17-8-5-42R	43-015-30686	Producing	State
State of Utah 17-8-7-34	43-015-30621	Producing	State
State of Utah 17-8-8-14	43-015-30673	Producing	State
State of Utah 36-138	43-015-30550	Producing	State
State of Utah 36-139	43-015-30530	Producing	State
State of Utah AA 07-105	43-015-30497	Producing	State
State of Utah AA 07-106	43-015-30396	Producing	State
State of Utah AA 07-146	43-015-30569	Producing	State
State of Utah BB 04-116	43-015-30503	Producing	State
State of Utah BB 05-107	43-015-30479	Producing	State
State of Utah BB 05-108	43-015-30480	Producing	State
State of Utah BB 05-109	43-015-30481	P&A	State
State of Utah BB 05-110	43-015-30482	Producing	State
State of Utah BB 08-113	43-015-30496	Shut In	State
State of Utah BB 09-119	43-015-30437	Producing	State
State of Utah BB 09-120	43-015-30444	Producing	State
State of Utah CC 03-161	43-015-30552	Producing	State
State of Utah CC 10-123	43-015-30454	Producing	State
State of Utah CC 10-124	43-015-30438	Producing	State
State of Utah FF 10-125	43-015-30458	Producing	State
State of Utah FF 11-129	43-015-30459	Producing	State
State of Utah FF 11-130	43-015-30462	Shut In	State

Utah Wells Surface Commingled at Huntington CDP

State of Utah FO 02-186	43-015-30533	Producing	State
State of Utah FO 02-188	43-015-30553	Producing	State
State of Utah GG 03-122	43-015-30499	Producing	State
State of Utah GG 04-115	43-015-30504	Producing	State
State of Utah HH 03-133	43-015-30500	Producing	State
State of Utah II 36-95	43-015-30509	Producing	State
State of Utah II 36-96	43-01530508	Shut In	State
State of Utah KK 32-144	43-015-30567	Producing	State
State of Utah QQ 31-201	43-015-30592	Producing	State
State of Utah SS 22-165	43-015-30520	Producing	State
State of Utah T 36-10	43-015-30268	Producing	State
State of Utah T 36-100	43-015-30506	Producing	State
UP&L 06-102	43-015-30441	Producing	State
UP&L 06-103	43-015-30483	Producing	State
UP&L 06-104	43-015-30442	Producing	State
UP&L Federal 01-101	43-015-30511	Producing	Federal
Utah Federal 01-205D	43-015-30589	Producing	Federal
* Utah Federal 16-7-35-21	43-015-30602	Producing	Federal
* Utah Federal 16-7-35-32	43-015-30603	Producing	Federal
* Utah Federal 17-7-12-22D	43-015-30605	Producing	Federal
Utah Federal 17-7-12-24D	43-015-30604	Producing	Federal
* Utah Federal 17-7-12-42	43-015-30591	Producing	Federal
Utah Federal 17-7-12-43	43-015-30601	Producing	Federal
Utah Federal 17-7-3-41D	43-015-30697	Producing	Federal
Utah Federal KK 01-140	43-015-30507	Producing	Federal
Utah Federal KK 01-141	43-015-30559	Producing	Federal
Utah Federal M 06-25	43-015-30292	Producing	Federal
WH Leonard 15-127	43-015-30485	Producing	State
Wm S Ivie 09-118	43-015-30443	Producing	State
Zion's Federal 35-135R	43-015-30521	Producing	Federal
* Zion's Federal 17-7-2-11	43-015-30590	Producing	Federal
Zion's Federal 35-137	43-015-30587	Producing	Federal

Utah Wells Surface Commingled at Orangeville CDP

Well Name	API #	Status	Lease	Notes
Curtis D&D 14-54	43-015-30319	Shut In	Federal	
Curtis L&M 10-58	43-015-30310	Shut In	Federal	
Curtis L&M 15-67	43-015-30325	Producing	Federal	
Federal A 18-7-26-12	43-015-30445	Producing	Federal	
Federal A 26-02	43-015-30244	Shut In	Federal	
Federal A 26-04	43-015-30246	Shut In	Federal	
Federal A 34-07	43-015-30249	Producing	Federal	
Federal A 35-05	43-015-30248	Producing	Federal	
Federal A 35-06	43-015-30247	Producing	Federal	
Federal A 35-89	43-015-30446	Producing	Federal	
Federal B 21-03	43-015-30243	Shut In	Federal	
Federal C 18-7-23-23R	43-015-30629	Producing	Federal	
Federal C 23-08	43-015-30245	Producing	Federal	
Federal P 03-92	43-015-30448	Producing	Federal	
Federal P 03-93	43-015-30449	Producing	Federal	
Federal T 18-07-22-34	43-015-30452	Producing	Federal	
Federal T 22-69	43-015-30451	Producing	Federal	
Federal T 27-87	43-015-30456	P&A	Federal	
Ferron St 4-36-18-7	43-015-30253	Producing	Federal	Operator: Merrion Oil & Gas
Jensen AL 27-09	43-015-30259	Shut In	State	
Jones D&A 09-59	43-015-30329	Producing	Federal	
Jones D&A 15-68	43-015-30318	Shut In	State	
Klinkhammer 1	43-015-30610	Shut In	Federal	Operator: Merrion Oil & Gas
Norris RG 14-40	43-015-30324	Producing	Federal	
Peacock 07-64	43-015-30327	Producing	Federal	
Peacock P&K 08-62	43-015-30320	Producing	Federal	
Peacock Trust 08-61	43-015-30326	Producing	Federal	
Peacock Trust 08-63	43-015-30328	Producing	Federal	
Peacock Trust 09-60	43-015-30321	Producing	Federal	
State of Utah 01-97	43-015-30498	Producing	State	
State of Utah 17-7-36-33R	43-015-30687	Producing	State	
State of Utah 17-8-19-11D	43-015-30695	P&A	State	
State of Utah 18-7-2-33R	43-015-30674	Producing	State	
State of Utah DD 31-98	43-015-30439	Producing	State	
State of Utah II 36-95	43-015-30599	Producing	State	
State of Utah II 36-96	43-015-30508	P&A	State	
State of Utah U 02-11	43-015-30270	Producing	State	
State of Utah U 02-48	43-015-30306	Producing	State	
State of Utah U 02-49	43-015-30309	P&A	State	
State of Utah U 02-50	43-015-30308	Producing	State	
State of Utah X 16-65	43-015-30312	Shut In	State	
State of Utah X 16-66	43-015-30311	Producing	State	
UP&L 14-53	43-015-30313	Producing	State	
UP&L 14-55	43-015-30314	Producing	Federal	
UP&L 23-51	43-015-30315	Producing	Federal	
UP&L 24-57	43-015-30316	Producing	State	
USA 03-74	43-015-30383	Producing	Federal	

Utah Wells Surface Commingled at Orangeville CDP

USA 03-75	43-015-30384	Producing	Federal	
USA 11-72	43-015-30387	Producing	Federal	
USA 18-7-11-23	43-015-30640	Producing	State	
USA 34-80	43-015-30389	Shut In	Federal	
USA 34-82	43-015-30390	Producing	Federal	
Utah Federal 17-7-35-42	43-015-30641	Drilling	Federal	
Utah Federal 18-7-27-44R	43-015-30628	Producing	Federal	
Utah Federal 18-7-9-11	43-015-30639	Producing	Federal	
Utah Federal D 34-12	43-015-30282	Producing	Federal	
Utah Federal D 35-13	43-015-30285	Producing	Federal	
Utah Federal D 35-14	43-015-30286	Producing	Federal	
Utah Federal D 35-15	43-015-30287	Producing	Federal	
Utah Federal H 06-21	43-015-30294	TA	Federal	
Utah Federal P 10-42	43-015-30276	Producing	Federal	
Utah Federal P 10-43	43-015-30277	Producing	Federal	
Utah Federal P 10-47	43-015-30258	Producing	Federal	
Utah Federal Q 04-44	43-015-30280	Producing	Federal	
Utah Federal R 09-45	43-015-30275	Producing	Federal	
Utah Federal S 08-46	43-015-30274	Producing	Federal	
Utah State 01-76	43-015-30381	Producing	State	
Utah State 36-78	43-015-30382	Producing	State	

igion Wells

Page 1 of 4

FIELD ESTIMATED PRODUCTION										ACTUAL ALLOCATED SALES									
Wells	Days On	MONTHLY WATER PRODUCTION	Costal Statement	PROD %	FIELD EST PROD	Irr Gas	Lse Use Gas	Vented Gas	VENTED GAS	ADJ (1)	FIELD ESTIMATED SALES	ALLOCATED SALES	Lse Use Gas	VENTED CO2	TOTAL VENTED	TOTAL ADJ (1)	FIELD PRODUCTION		
B21-03	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
A26-02	25	88	490	0.001657751	490	39	13	15	15	671	423	432	52	15	15	67	499		
C23-08	30	3432	9140	0.030922051	9140	45	236	437	437	7181	8422	8062	281	437	437	718	8780		
A26-04	15	0	68	0.00023005	68	23	2	2	2	26	42	60	24	2	2	26	86		
A35-06	30	121	29099	0.09844307	29099	45	750	1706	1706	2501	26597	25665	795	1706	1706	2501	28166		
A35-05	18	700	299	0.00097775	299	27	139	361	361	545	4838	4748	184	361	361	545	5293		
A34-07	30	2845	5383	0.01821153	5383	45	210	6	6	220	81	123	214	6	6	220	343		
P10-47	30	734	391	0.00047026	139	210	4	0	0	0	0	0	0	0	0	0	0		
A27-09	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
U02-11	30	50211	15291	0.05173184	15291	45	394	1255	1255	1694	13597	13487	439	1255	1255	1694	15181		
S08-46	29	11	519	0.00175586	519	293	13	230	230	448	73	458	216	230	230	448	904		
R09-45	30	36	444	0.00150212	444	210	11	102	102	323	121	392	221	102	102	323	715		
P10-42	29	7809	819	0.0027708	819	44	21	144	144	206	610	722	65	144	144	206	931		
P10-43	30	3050	605	0.00204681	605	45	16	11	11	125	54	63	14	11	11	125	188		
Q04-44	16	5442	71	0.0002402	71	12	2	11	11	125	54	63	14	11	11	125	188		
D34-12	24	2583	1471	0.00491662	1471	36	38	126	126	200	1271	1297	74	126	126	200	1497		
D35-13	30	142110	293	0.00099126	293	36	8	57	57	101	192	258	44	57	57	101	1207		
U35-14	24	647	293	0.00099126	293	36	8	57	57	101	192	258	44	57	57	101	359		
D35-15	30	1830	20903	0.07071811	20903	45	539	1326	1326	1910	18993	18436	544	1326	1326	1910	20346		
H06-21	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
U02-48	25	75271	2310	0.00781509	2310	42	60	148	148	250	2060	2037	102	148	148	250	2287		
U02-50	30	706	2703	0.00914457	2703	45	70	165	165	280	2423	2384	115	165	165	280	2684		
U02-49	15	173	347	0.00173395	347	23	9	18	18	49	296	305	31	18	18	49	355		
10-58	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
X16-66	28	307	290	0.00098112	290	42	7	38	38	87	203	256	49	38	38	87	343		
X16-65	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
14-53	30	298	827	0.00279787	827	45	21	50	50	116	711	729	66	50	50	116	845		
14-55	30	9023	65522	0.41965343	124042	90	3196	7739	7739	11025	113017	109405	3266	7739	7739	11025	120430		
14-55A	30	0	58520	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
23-51	30	175	259	0.00091007	259	45	7	9	9	61	208	237	52	9	9	61	258		
24-57	30	254	581	0.00230393	581	45	18	22	22	85	596	601	63	22	22	85	686		
15-68	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
14-54	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
08-62	29	23	491	0.00166113	491	44	13	178	178	235	256	433	59	178	178	235	660		
09-60	29	1445	1074	0.00363351	1074	44	28	294	294	365	709	947	71	294	294	365	1312		
14-40	30	4320	2701	0.0091379	2701	45	70	154	154	269	2432	2382	115	154	154	269	2851		
15-67	26	202	261	0.0008863	261	39	7	14	14	60	201	230	46	14	14	60	290		
08-61	30	478	9427	0.03189301	9427	45	243	528	528	816	8611	8315	288	528	528	816	9131		
07-54	30	1092	1557	0.00560589	1557	45	43	495	495	593	1074	1461	88	495	495	593	2044		
08-63	30	264	1654	0.00559574	1654	45	43	777	777	865	789	1459	88	777	777	865	2324		
09-59	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
01-76	30	3108	4980	0.01684812	4980	45	128	326	326	499	4481	4392	173	326	326	499	4891		
36-78	30	903	5802	0.01962907	5802	45	150	380	380	575	5227	5117	195	380	380	575	5692		
03-74	27	24620	1325	0.00448258	1325	41	34	30	30	105	1220	1169	75	30	30	105	1274		
03-75	30	5879	4396	0.01487235	4396	45	113	298	298	457	3939	3877	158	298	298	457	4334		
11-72	30	45297	922	0.00311927	922	45	24	177	177	246	676	813	69	177	177	246	1059		
34-80	15	44	113	0.0003823	113	24	3	21	21	48	65	100	27	21	21	48	148		
34-82	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
31-98	30	10	1482	0.00501384	1482	45	38	133	133	216	1268	1307	83	133	133	216	1523		
A35-89	30	9902	34803	0.11774399	34803	45	897	2021	2021	2963	31840	30696	942	2021	2021	2963	33659		
P03-92	30	1184	386	0.00299748	386	45	23	89	89	157	729	781	68	89	89	157	938		
P03-93	28	9434	546	0.00218552	546	42	17	96	96	155	491	570	59	96	96	155	725		
T22-59	30	320	1130	0.00382297	1130	45	29	58	58	32	998	997	74	58	58	32	1129		
T27-87	30	574	546	0.0018472	546	45	14	27	27	86	460	482	59	27	27	86	568		
01-97	30	0	1194	0.00403949	1194	0	31	73	73	104	409	415	12	73	73	104	1157		
36-95	30	61	470	0.00159008	470	0	12	49	49	61	409	415	12	49	49	61	476		
36-95	30	1503	1260	0.00426278	1260	0	32	130	130	162	1098	1111	32	130	130	162	1273		
MERRON GAS WELLS																			
hammer	29	10537	481	0.0016273	481	0	12	15	15	27	454	424	12	15	15	27	451		
al	30	985	493	0.0016679	493	0	0	28	28	28	465	435	0	28	28	28	463		
4-36-18-7	30	985	493	0.0016679	493	0	0	28	28	28	465	435	0	28	28	28	463		
SALES LESS MERRION WELLS																			
259,844																			

PIPELINE

1E WELLS FROM OCASTA STATEMENT

	20777			SALES DIFFERENCE	8676	JC137 54
	0					
	7604			7604	0	
	2448		2448			
	0		0			
Id statement + memon	974					
	31833	295582	2448	7604	0	

395211	597033	597137	4379	14575	59724	59724	790771	518050	514853	9355	59724	59724	79079	593932
--------	--------	--------	------	-------	-------	-------	--------	--------	--------	------	-------	-------	-------	--------

OCT 12 2004

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: Various Leases
2. NAME OF OPERATOR: XTO ENERGY INC. <i>N2615</i>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Bldg K, Sui. Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE:		8. WELL NAME and NUMBER: See attached list
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		9. API NUMBER: Multiple
COUNTY: Emery		10. FIELD AND POOL, OR WILDCAT: Buzzard Bench
STATE: UTAH		

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective August 1, 2004, the operator changed from Chevron U.S.A. Inc. to XTO ENERGY INC. for all wells on the attached list.

BLM #579173

State and Fee Bond #104312762

RECEIVED
MAY 18 2007

DIV. OF OIL, GAS & MINING

Kenneth W. Jackson

Kenneth W. Jackson

Regulatory Specialist ChevronTexaco for Chevron U.S.A. Inc. *N0210*

NAME (PLEASE PRINT) *James L. Death* TITLE *Vice President - Land*
SIGNATURE *James L. Death* DATE *8/16/04*

(This space for State use only)

APPROVED *9/30/2004**Earlene Russell*

Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

(See instructions on Reverse Side)

(5/2000)

RECEIVED
SEP 28 2004

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, re-enter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <u>CONFIDENTIAL</u>		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-67532
2. NAME OF OPERATOR: XTO ENERGY INC.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 2700 Farmington Ave. Bldg K CITY Farmington STATE NM ZIP 87401		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1815' FNL & 897' FWL QTRQTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SWNW 26 18S 07E		8. WELL NAME and NUMBER: FEDERAL A 18-7-26 #12
PHONE NUMBER: (505) 324-1090		9. API NUMBER: 4301530445
COUNTY: EMERY		10. FIELD AND POOL, OR WILDCAT: BUZZARD BENCH ABO
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: <u>SURFACE</u>
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<u>COMMINGLE</u>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. proposes to surface commingle the following two wells into our Orangeville CDP:

Federal A 18-7-26 #12; Sec 26-T18S-R07E; 1815' FNL & 897' FWL; 43-015-30445; UTU-67532; Buzzard Bench
Federal T 18-7-22 #34; Sec 22-T18S-R07E; 539' FSL & 1831' FEL; 43-015-30452; UTU-68535; Buzzard Bench

Both of these wells have their own wellhead allocation meter. Both wells will have the sales point or custody transfer at the Orangeville System.

COPY SENT TO OPERATOR
Date: 7-11-05
Initials: CHD

NAME (PLEASE PRINT) HOLLY C. PERKINS TITLE REGULATORY COMPLIANCE TECH
SIGNATURE Holly C. Perkins DATE 6/23/2005

(This space for State use only)

Accepted by the
Utah Division of
Oil, Gas and Mining

Federal Approval Of This
Action Is Necessary

RECEIVED
JUN 29 2005

DIV. OF OIL, GAS & MINING

(5/2000)

Date: 7/18/05
By: Dustin Ducet (See Instructions on Reverse Side)

Dustin
Ducet ??

IN WELLS FROM COASTAL STATEMENT

	0	302425			
	38990				
	104	104			
	256029				
s Check #	0				
s Check #2	0			0	
	7383			7383	0
	1931		1930 5		
	0				
	304437	302529	1930 5	7383	0

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☒ OTHER _____

2. NAME OF OPERATOR:
XTO ENERGY INC.

3. ADDRESS OF OPERATOR:
382 CR 3100 CITY AZTEC STATE NM ZIP 87410

PHONE NUMBER:
(505) 333-3100

4. LOCATION OF WELL

FOOTAGES AT SURFACE: MULTIPLE

COUNTY: EMERY

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

18S 7E 22

STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: SURFACE
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	COMMINGLE

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

XTO Energy Inc. applied for surface commingle on the attached list of wells on 7/5/07 and State of UT DOGM approval was received on 7/13/07. Due to the rejection of the Federal application, XTO would like to withdraw the commingling application and subsequent work will not be done.

NAME (PLEASE PRINT) LORRI D. BINGHAM

TITLE REGULATORY COMPLIANCE TECH

SIGNATURE

DATE 9/23/2008

(This space for State use only)

RECEIVED
SEP 29 2008

Utah Wells Surface Commingled at Orangeville CDP				
Well Name	API #	Status	Lease	Notes
Curtis D&D 14-54	43-015-30319	Shut In	Federal	
Curtis L&M 10-58	43-015-30310	Shut In	Federal	
Curtis L&M 15-67	43-015-30325	Producing	Federal	
Federal A 18-7-26-12	43-015-30445	Producing	Federal	
Federal A 26-02	43-015-30244	Shut In	Federal	
Federal A 26-04	43-015-30246	Shut In	Federal	
Federal A 34-07	43-015-30249	Producing	Federal	
Federal A 35-05	43-015-30248	Producing	Federal	
Federal A 35-06	43-015-30247	Producing	Federal	
Federal A 35-89	43-015-30446	Producing	Federal	
Federal B 21-03	43-015-30243	Shut In	Federal	
Federal C 18-7-23-23R	43-015-30629	Producing	Federal	
Federal C 23-08	43-015-30245	Producing	Federal	
Federal P 03-92	43-015-30448	Producing	Federal	
Federal P 03-93	43-015-30449	Producing	Federal	
Federal T 18-07-22-34	43-015-30452	Producing	Federal	
Federal T 22-69	43-015-30451	Producing	Federal	
Federal T 27-87	43-015-30456	P&A	Federal	
Ferron St 4-36-18-7	43-015-30253	Producing	Federal	Operator: Merrion Oil & Gas
Jensen AL 27-09	43-015-30259	Shut In	State	
Jones D&A 09-59	43-015-30329	Producing	Federal	
Jones D&A 15-68	43-015-30318	Shut In	State	
Klinkhammer 1	43-015-30610	Shut In	Federal	Operator: Merrion Oil & Gas
Norris RG 14-40	43-015-30324	Producing	Federal	
Peacock 07-64	43-015-30327	Producing	Federal	
Peacock P&K 08-62	43-015-30320	Producing	Federal	
Peacock Trust 08-61	43-015-30326	Producing	Federal	
Peacock Trust 08-63	43-015-30328	Producing	Federal	
Peacock Trust 09-60	43-015-30321	Producing	Federal	
State of Utah 01-97	43-015-30498	Producing	State	
State of Utah 17-7-36-33R	43-015-30687	Producing	State	
State of Utah 17-8-19-11D	43-015-30695	P&A	State	
State of Utah 18-7-2-33R	43-015-30674	Producing	State	
State of Utah DD 31-98	43-015-30439	Producing	State	
State of Utah II 36-95	43-015-30509	Producing	State	
State of Utah II 36-96	43-015-30508	P&A	State	
State of Utah U 02-11	43-015-30270	Producing	State	
State of Utah U 02-48	43-015-30306	Producing	State	
State of Utah U 02-49	43-015-30309	P&A	State	
State of Utah U 02-50	43-015-30308	Producing	State	
State of Utah X 16-65	43-015-30312	Shut In	State	
State of Utah X 16-66	43-015-30311	Producing	State	
UP&L 14-53	43-015-30313	Producing	State	
UP&L 14-55	43-015-30314	Producing	Federal	
UP&L 23-51	43-015-30315	Producing	Federal	
UP&L 24-57	43-015-30316	Producing	State	
USA 03-74	43-015-30383	Producing	Federal	

RECEIVED

SEP 29 2008

DIV. OF OIL, GAS & MINING

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-68538
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: XTO ENERGY INC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410		8. WELL NAME and NUMBER: FEDERAL T 18-7-22-34
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0539 FSL 1831 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSE Section: 22 Township: 18.0S Range: 07.0E Meridian: S		9. API NUMBER: 43015304520000
PHONE NUMBER: 505 333-3159 Ext		9. FIELD and POOL or WILDCAT: BUZZARD BENCH
COUNTY: EMERY		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 5/4/2011	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="text-align: center; padding: 20px;"> XTO Energy Inc. has returned this well to production @ 1430 hours on Wednesday, 05/04/2011. </div> <div style="text-align: right; padding: 20px;"> Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY </div>		
NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 505 333-3642	TITLE Regulatory Compliance Tech
SIGNATURE N/A	DATE 5/6/2011	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-68538
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: XTO ENERGY INC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410		8. WELL NAME and NUMBER: FEDERAL T 18-7-22-34
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0539 FSL 1831 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSE Section: 22 Township: 18.0S Range: 07.0E Meridian: S		9. API NUMBER: 43015304520000
PHONE NUMBER: 505 333-3159 Ext		9. FIELD and POOL or WILDCAT: BUZZARD BENCH
COUNTY: EMERY		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> APD EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 10/12/2011		
<input type="checkbox"/> SPUD REPORT Date of Spud:		
<input type="checkbox"/> DRILLING REPORT Report Date:		
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. XTO Energy Inc. has returned this well to production @ 11:00 a.m. on 10/12/2011.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY		
NAME (PLEASE PRINT) Dolena Johnson	PHONE NUMBER 505 333-3164	TITLE Regulatory Compliance Tech
SIGNATURE N/A	DATE 10/13/2011	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-68538
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: XTO ENERGY INC		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 382 Road 3100 , Aztec, NM, 87410		8. WELL NAME and NUMBER: FEDERAL T 18-7-22-34
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0539 FSL 1831 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSE Section: 22 Township: 18.0S Range: 07.0E Meridian: S		9. API NUMBER: 43015304520000
PHONE NUMBER: 505 333-3145 Ext		9. FIELD and POOL or WILDCAT: BUZZARD BENCH
COUNTY: EMERY		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 4/11/2012	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. XTO Energy Inc. has returned this well to production @ 1100 hours, 4/11/2012.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY May 03, 2012		
NAME (PLEASE PRINT) Barbara Nicol	PHONE NUMBER 505 333-3642	TITLE Regulatory Compliance Tech
SIGNATURE N/A	DATE 4/12/2012	